

Butte Falls, Oregon  
December 12, 1959

County Surveyor  
Jackson County Court House  
Medford, Oregon

Dear Sir;

Please record the following information pertaining to the United States public land surveys.

I, Duane A. Smeltzer on December 12, 1959 restored the existent 1/4 section corner common to Sections 8 and 9 T34S R4W, W.M.

The monument is a Cadastral Brass-cap pipe in a mound of stones. Magnetic declination; 20°E.

As evidence is a Cedar 17" bears N36°E 59 links, scribed 1/4 S 9 BT on butt. A Cedar 52" bears N26°W 39 links, scribed 1/4 S 8 BT on butt, Both being established by Cadastral surveyors in 1958. Also as evidence are the original B.T. A cedar 24" bears S23°E 57 links (by original notes) and a Cedar 18" bears S38°W 20 links (by original notes). Both contain faces but scribes are not visible.

Sincerely yours,

REGISTERED  
OREGON  
LAND SURVEYOR

*Duane A. Smeltzer*

OCTOBER 24, 1958  
DUANE A. SMELTZER  
461

