

Survey No. 13587

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

Survey for: Sam Dawson
P.O. Box 477
Jacksonville, Oregon 97530

Location: Located in all quarters of Section 16,
Township 38 South, Range 3 West of the Willamette
Meridian, Jackson County, Oregon

Purpose: To survey, monument and mark the lines of that
parcel described in Instrument Number 50-10657
per clients request

Procedure: In a closed traverse I tied the controlling
monuments, proportioned the lotting in Section
16 as shown on the 1909 G.L.O. plat of the
survey and retracement of part of Township 38
South, Range 3 West of the Willamette
Meridian under Contract Number 790 and set the
monuments to the North half of Government Lot
3 in said Section as shown on the accompanying
plat.

The South Quarter corner of Section 16 only
was single proportioned between the calculated
southwest corner and the southeast corner of
Section 16 for distance and placed on the line
between the North Quarter corner of Section 21
only and the Northeast corner of Section 21.


Bearing trees tied for the South Quarter
corner to Section 16 only are as follows:
16 inch white oak bears N 4.38'36"E, 17.3 feet
8 inch white oak bears N 67.30'19"E, 24.8 feet
17 inch white oak bears S 25.03'56"E, 27.6 feet
2 1/2 inch Brass Disk being the North 1/4
corner to Section 21 only bears N 89.02'35"W,
76.84 feet.




Surveyed by: Farber & Sons, Inc.

Farber Surveying
908 East Jackson Street
Medford, Oregon 97504

Date: July 22, 1993



[Handwritten Signature]



Expires 12/31/93