

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

13605

TO COMPLY WITH PARAGRAPH 209.130
OREGON REVISED STATUTES

History of Original Establishment:

The original survey of the subdivision Township 32 South, Range 3 East, Willamette Meridian, Jackson County, Oregon was surveyed by Rufus S. Moore under Contract No. 496 dated June 17, 1884. The Jackson County Surveyor perpetuated this corner from evidence in 1954. Joseph Gawron, BLM, reestablished this corner under surveys for Group No. 350, in 1962 .

Description of corner evidence found:

The quarter section corner for sections 11, 12, Township 32 South, Range 3 East, monumented with a 1 inch diam. iron pipe with a 2 inch expander filled with pot metal attached, protruding 6 inches above ground marked as shown. Found the original basalt stone, 16 X 10 X 8 inches marked 1/4 alongside.

At the corner point, I found a Jackson County monument, marked:

T32S	R3E
4S	BLM
11	12
1962	
CS 1/4 COR	1954

And the following accessories:

I. Cedar, 36 inch diameter, bears S. 57°09'E., 50.30 ft. distance, with healed blaze.

Fir Snag, 32 inch diameter, bears S. 33°58'E., 38.60 ft. distance, with no visible scribe.

Description of monument and accessories I establish to perpetuate the original location of this corner:

I marked the following new accessory:

Fir, 18 inches in diameter, bears N. 81°06'W., 22.20 ft. distance, marked 1/4 S11 BT with brass washer marked LS 2332.

Basis of Bearing: Solar Observation.

June 10, 1993

STEPHAN L. BAROTT
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON CERTIFICATE NO. 2332

