

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

13 606

TO COMPLY WITH PARAGRAPH 209.130
OREGON REVISED STATUTES

History of Original Establishment:

The original survey of the south boundary Township 39 South, Range 3 West, Willamette Meridian, Jackson County, Oregon was surveyed by Sewall Truax under Contract No. 74 dated June 11, 1857. The Jackson County Surveyor perpetuated this corner from evidence in 1953. Joseph Gawron remonumented this corner under surveys for Group 350 approved 08/16/1965. Kurt Weaver, LS 1679, occupied this corner during a survey for Rogue River Nat'l Forest in 1981, and filed with the County Surveyor as record Survey No. 8682.

Description of corner evidence found:

The section corner for sections 32,33 (Township 39 South), and 4,5 (Township 40 South), Range 3 West. Corner is 2 inches below the road surface near McKee Bridge store.

At the corner point, I found a Bureau of Land Management brass cap monument, marked:

T39S	R3W
S32	S33
S 5	S 4

T 40 S
1964

And the following accessories:

Southwest corner of a foundation of a wood frame house bears N.64°24'E., 191.95 feet distance. (Weaver record N.64°24'E., 192.00 feet. This is the basis of bearing for this current survey)

The base of a concrete block chimney on McKee Bridge store bears S.41°18' W., 61.90 feet distance.

Description of monument and accessories I establish to perpetuate the original location of this corner:

I marked the following new accessories:

Brass plaque located at McKee Bridge: The "dot in the i" in "society" bears S.6°56'W., 338.69 feet distance.

Fire place in McKee Bridge campground: Stamped an "X", inside the door frame of a metal clean out box, bears N.3°27'E., 187.31 feet distance.

Basis of Bearing: Solar Observation from Record Survey No. 8682.

June 10, 1993

STEPHAN L. BAROTT
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON CERTIFICATE NO. 2332

