

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

TO COMPLY WITH PARAGRAPH 209.130
OREGON REVISED STATUTES

13 607


History of Original Establishment:

The original subdivision survey of the Township 40 South, Range 3 West, Willamette Meridian, Jackson County, Oregon was surveyed by Samuel W. Lackland under Contract No.429 dated Sept. 20, 1882. Joseph Gawron remonumented the 1/4 corner for sections 4 and 5, as diagramed below under surveys for Group 350 approved 08/16/1965. Kurt Weaver, LS 1679, occupied this corner during a survey for Rogue River Nat'l Forest in 1981. Weaver filed this survey with the Jackson County Surveyor as Record Survey No. 8682.

Description of corner evidence found:

The quarter corner for sections 4 and 5, Township 40 South Range 3 West.

At the corner point, I found a Bureau of Land Management brass cap monument, marked:



And the following accessories:

A White Oak, 28 ins. diam., bears N.19°02'E., 23.50 feet distance, mkd.with healed blaze on a hollow tree. (1882 Lackland)

A forked White Oak, 17 ins.diam., bears N.70°43'W.,78.53 feet distance, mkd. with a decayed blaze. Tree is hollow. (1882 Lackland)

A White Oak, 6 ins. diam., bears N.65°15'E., 14.59 feet distance, mkd. with scribing "1/4S4BT" on partially healed blaze. (1965 Gawron)

Description of monument and accessories I establish to perpetuate the original location of this corner:

I marked the following newaccessory:

Large rock, size indeterminate, bears S.86°40'W., 58.47 feet distance, mkd. "BXO", with a P-K nail in the center of the X.

Basis of Bearing: Solar Observation from Record Survey No. 8682.

June 15, 1993

STEPHAN L. BAROTT
REGISTERED PROFESSIONAL LAND SURVEYOR
OREGON CERTIFICATE NO. 2332

