

NARRATIVE REPORT

SURVEY

Establishment of Quarter Section Corner  
Common to Sections 10 and 11 in T. 36 S. R. 3 W. W. M.  
Jackson County, Oregon.

No monument or bearing trees being found, the position of the Quarter Section corner was established by single proposition measurement on the Section line.

Line was established by direct sighting between flags at established corners found at corner common to Sections 2,3,10, and 11 North and Sections 10,11,14, and 15 South, clearly visible from one to the other. Chaining was carried on true line with the exception of triangulation across Rogue River.

A 1 1/2" x 30" aluminum pipe was driven at equal distance between corners, being about 60 feet north of the then Northerly bank of Rogue River. A 1 1/4" diameter Jack Pine with blaze is S. 30° W. 27.0 feet, and a 1/2" x 24" rebar steel pin is 117.38 feet North on Section line,

February 24, 1960

Hugh C. Ingle  
Civil engineer.

NOTE: OVERALL DISTANCE MEASURED  
5310.36 FT.

