



SOURCES:

COUNTY SURVEYOR,  
"REESTABLISHED CORNERS,"  
COUNTY ROAD ENGINEER  
MAP OF NORTH RIVER RD.  
FIELD NOTES - N. RIVER RD.  
" " " WARD CR. RD.  
CONTRACT OF SALE  
10 AUG 1946

1377

<b>CAMERON PARR</b>	
DATE 4 FEB 1960	REGISTERED OREGON LAND SURVEYOR  <i>Lee B. Coon</i>
SEC. 22, TWP. 36, SRGE. 4 W.	
SCALE 1" = 100 FT.	MAY 2, 1958 <b>LEE B. COON</b> 439
DRAWN BY LBC	
COUNTY JACKSON	

**LEE B. COON, SURVEYOR**  
GRANTS PASS, OREGON

LEE B. COON  
REGISTERED SURVEYOR  
PHONE BR 9-2360

POST OFFICE BOX 451

GRANTS PASS, OREGON

SURVEY FOR CAMERON PARR

ROGUE RIVER, ORE.

4 FEBRUARY 1960

Description of Control

The point of prime control for this survey is the reestablished  $\frac{1}{4}$  cor. of Secs. 15 and 22, T.36 S., R. 4 W., as described in the records of the County Surveyor. The line betw. secs. 15 and 22 was est. by sighting the West  $\frac{1}{16}$  cor. of secs. 15 and 22, a  $\frac{3}{4}$ " pipe set flush with the ground. The record bearing for this line is accepted and used as a meridean for this survey. All other bearings are determined by angulation carried forward from this line.

The P.I.'s for the county roads were reestablished from the field record of the county road engineer's surveys, and linked by a traverse initiated at the  $\frac{1}{4}$  cor. A difference was noted between the meridean for the roads and the section line, but persistantly cloudy weather made it impossible to make observations.

The center-line of sec. 22 was not established and no monuments were set on the easterly boundary.

The authority for this survey is the CONDITIONAL SALE CONTRACT TO CAMERON A . PARR, dated 10 Aug. 1946. An unrecorded monument was found on the westerly right-of-way line of North River Road, with a cap Mkd. " U 3 " , and precisely agreed with this survey.

