

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

FOR: SHELL OIL CO.

PURPOSE: To monument the consolidated boundaries of the following described tracts:

1. The West 65' of the South 150 feet of that property described in Volume 233, Page 606 of the Deed Records of Jackson County, Oregon.
2. That property described in Volume 469, Page 373 of the Deed Records of Jackson County, Oregon.
3. The South 50' of that property described in Volume 295, Page 111, less the South 90 feet, as described in Volume 469, Page 373 of the Deed Records of Jackson County, Oregon.

PROCEDURE:

Established a true meridian from a mean of several previous surveys with solar bearings made by this office in this area. Then tied in the located center-line of the Jacksonville Highway to the re-established Quarter corner to Sections 25 and 26 and the North-North-east corner of Donation Land Claim No. 76 by traverse lines. From this basic information, calculated the position of the original property boundaries according to the deed descriptions monumenting the parcels as shown on the attached map.

It will be noted that there is no definite location for Ross Lane. The location of said road as shown on the map is a retracement of the road as the same was physically occupied in 1910. Because of the possibility of future road widening, this exact road centerline was not determined on this survey.

The record lap along the West line of the surveyed parcel will increase from 0.95 feet to 5.60 feet if the Matlack description is interpreted as running "South along the East line of DLC # 76" instead of "due South."

May 1960

