



MAP OF SURVEY
 In the S.E. 1/4 of the S.W. 1/4 of
 Section 5, T. 39 S., R. 4 W., W.M.
 Jackson County, Oregon

SURVEY FOR:
 George Rice
 4599 Thompson Creek Road
 Applegate, OR 97530

SURVEY BY:
 L.J. Friar & Associates, P.C.
 Consulting Land Surveyors
 304 South Holly Street
 Medford, Oregon 97501
 Phone: (503) 772-2782

LEGEND:
 ⊙ - Found BLM brass capped monument & accessories.
 ● - Found 5/8" iron pin w/ plastic cap mkd. MOFFIT PLS944 per RS8455.
 ○ - Set 5/8" x 30" iron pin with plastic cap mkd. L.J. FRIAR & ASSOC.
 See narrative for accessories to fractional corner set.
 -X-X- - Fence line.
 RS - Recorded Survey #.

BASIS OF BEARINGS: Survey No. 8455. UNIT OF MEASUREMENT - Feet
 DATE: November 2, 1994 SCALE: 1" = 100'

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: To survey and monument the North line of Taxlot 2003 per the client's request.

PROCEDURE: From control and monuments established by this office during Survey No. 8455 calculated the position of the subject corners and set same. Set witness corner in the fence line along Thompson Creek Road. Those monuments found as well as those set are as shown hereon.

Accessories to fractional corner:
 From the CSSS 1/256 corner of Section 5:
 A 4" Fir bears S. 80° E., 7.5', mkd. "XBT"
 An 8" Fir bears S. 32° W., 8.7', mkd. "CSSS1/256S5BT".

RECEIVED
 Date: 12-15-94 By: [Signature]
 This survey consists of:
 1 sheet(s) Map
 0 Narrative
 JACOB COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
 [Signature]
 OREGON
 JULY 18, 1971
 LARRY J. FRIAR
 961
 Renewal Date 12-31-95

