


Survey of
 Lots 1-3, Block 1
 LAURELHURST ADDITION
 Medford, Oregon
 For: R.J. KEENEY
 By: Mark E. Boyden
 Sept. 1959



STEVENS AVE.

45.00

E.N.E. cor.
 D.L.C. 42
 Fd. 1" Iron pipe

LAKE

577.72

98.48

S 0°05' W

92.81

S 21°19' W

61.37

S 89°59'30" W

77.78

20.0

149.98

ALLEY

N 0°05' E

30.0'

100.00'

N 89°59'30" E

S 0°05' W

CRATER

Fd. spike & SALING

1433

SCALE: 1" = 30'

- Re-established Govt. cor.
- Fd. 1" Iron pipe
- Set 5/8" Iron pin

REGISTERED
OREGON
 AND SURVEYOR
Mark E. Boyden
 NOVEMBER 9 1961
 MARK E. BOYDEN
 281

RECEIVED
 JACKSON
 MAY 11 1960
 COUNTY
 ENGINEER-SURVEYOR

Survey Narrative to Comply With Paragraph 209.250

Oregon Revised Statutes

FOR: R. J. Keeney

PURPOSE: To monument the outside boundary corners of Lots 1 - 3,
Block 1 of LAURELHURST ADDITION to Medford, Oregon.

PROCEDURE:

From the 1" iron pipe found for the Northeast corner of Block 1 (See Recorded Survey No. 925) ran Southerly parallel to the East boundary of D. L. C. No. 42 a proportionate distance (between Saling Avenue and Stevens Avenue) of 149.98 feet; thence ran Westerly parallel with Stevens Avenue to intersect the East boundary of Crater Lake Avenue. The angle point on the West boundary of the said lots was determined on a record angle split from the PI (East-Northeast corner of D. L. C. #42).

It will be noted that the State highway curve data for this section of Crater Lake Avenue was not used, as no mention of additional land acquired by the Highway Department was found in the Keeney deed.

September 1959

