



1435

Survey Number-----

Survey Narrative to comply with paragraph 209.250 O.R.S.

Survey for Troy Drexler.

Purpose: To survey, what is known as the Ash Tract, lying in the West half of Section 5, Township 35 South, Range 1 West of the Willamette Meridian and lying West of the Rogue River Drive. To divide into 24 parcels.

Procedure: At the quarter corner, between Sections 5 and 8, I found a 3/4 inch iron pipe and 2 witness trees, in fair shape and corresponding to field notes. I ran North 89°56' West 613.1 feet to the West side of Rogue River Drive and continued on that course 2037.60 feet and found a rusty 1 1/4 inch pipe. Fence corner was North 39°39' East 6.0 feet. No bearing trees. Thence I ran North 0°05' East 2655.84 feet and set a 2"x2" Oak hub. Found a 18" Oak North 40° East 35 links and a pine stump hole South 50° West 44 links. Thence I ran North 0°05' East 2651.22 feet to corner 5,6,31 and 32. Drove a 2" Oak hub. Found a "20" Oak South 83° West 35 links and a 24" pine North 50° West 8 links; thence I ran East 2662.44 feet and drove a hub. Found a 24" black oak South 8° East 37 links.

These points were used as a base for the survey and monuments were set for the 24 parcels, as shown on the accompanying map.

Tom R. Pearce, Engineer No. 538

