



**SURVEY TO LOCATE SOUTH LINE OF SHAW PROPERTY**

IN SE 1/4 OF NE 1/4, SEC. 16, T36S, R4W, W. M.

12 MAY 1960

SCALE 1 INCH = 100 FEET

Drawn By R.D.G.

For R.M. THOMPSON

DONE FOR REDI-MIX CONCRETE

ROBERT M. THOMPSON

Consulting Engineer and Forester

611½ N.W. FOURTH STREET  
GRANTS PASS, OREGON

May 12, 1960

SURVEY NARRATIVE TO COMPLY WITH PAR. 209.250, O.R.S.

Survey to Locate South Line of Shaw Property in SE¼NE¼ Section 16,  
T36S, R4W, W.M.

For: Redi-Mix Concrete

Purpose: To establish monuments at corners on the South line  
of the above property.

Procedure: I establish a portion of the true East line of  
Section 16 by running from the East ¼ Corner to the North 1/16  
corner 16&15, both of which were set by the Jackson County  
Surveyor's Office in 1958. In accord with deed description in  
V485 P495 (Jackson Co. Deed Records) I set a 3/4 inch iron pipe  
on the Section line 418.0 feet N0°27'15"W of said ¼ Corner, at  
point described in deed as beginning of description. This point  
falls within the right-of-way of the East Evans Creek Road.

Since the deed description describes said section line as  
bearing due north, and the South line of the description as  
bearing due West, I turn off a right angle from said pipe and  
project a line to the east bank of the low water mark of Evans  
Creek, with distance described by deed as 398.2 feet. In order  
to establish a corner out of flood danger, I set a 3/4 inch iron  
pipe for a witness to southwest property corner, at a distance of  
370.0 feet S89°32'45"W from the beginning point of the description.

