



**MAP OF SURVEY**  
 Located in the N.E. 1/4 of Sec. 17, T.35 S.,  
 R.2 W., W.M. Jackson County, Oregon.

SURVEY FOR: SAFECO Insurance  
 P.O. Box 1900  
 Lake Oswego, OR 97035

SURVEY BY: L.J. Friar & Associates, P.C.  
 Consulting Land Surveyors  
 304 South Holly Street  
 Medford, Oregon 97501  
 Phone: (503) 772-2782

- LEGEND:
- ⊙ - Found County Surveyor's brass capped monument and accessories per re-estab's.
  - ⊗ - Found B.L.M. brass capped monument and accessories, not of record.
  - - Set 5/8" x 24" iron pin with plastic cap mkd. L.J. FRIAR & ASSOCIATES.
  - - Set 5/8" x 24" iron pin for reference object. See narrative below.

BASIS OF BEARINGS: Survey No. 12173.  
 DATE: June 28, 1995 UNIT OF MEASUREMENT: Feet SCALE: 1" = 100'

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: To set the East 1/16 corner on the North line of Section 17 and flag a line South from the E. 1/16 corner for a distance of 1320 feet.

PROCEDURE: From existing control established by this office during RS12173, calculated the position of the East 1/16 and set same. The Hull Mountain Fire destroyed any possible BT's in the area. Therefore no trees were scribed. As cost was a factor in this Survey, the client instructed us to flag a line South from this corner 1320 feet. This line is not intended to be the fractional Section line and the client is aware of this fact. The B.L.M. brass cap found has been recently set but is not of public record as of this date.

- Set references to the E. 1/16 corner:
- 1) 5/8" iron pin (no cap) bears S.0°01'17"W., 100.00'.
  - 2) 5/8" iron pin (no cap) bears S.81°11'47"W., 13.69'.

8/22/95 sc  
 1  
 0

REGISTERED PROFESSIONAL LAND SURVEYOR  
 James E. Hibbs  
 OREGON  
 JULY 17, 1986  
 JAMES E. HIBBS  
 2234  
 Renewal Date 6-30-97