

Survey No. 14695

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

Survey for: Louis and Anna Primavera
842 Linksvie Drive
Simi Valley, Ca. 93065

Location: Gold Rey Subdivision-Unit No. 2, Block 6, Lots 4,5 and 6, located in the northeast quarter of Section 13, Township 36 South, Range 3 West and the northwest quarter of Section 18, Township 36 South, Range 2 West of the Willamette Meridian, Jackson County, Oregon.

Purpose: To survey and monument the property line adjustment as approved by the Jackson County Department of Planning and Development.
File No. 95-224-PA

Procedure: Utilizing global positioning satellite observations and a Sokkia Set-4 total station with a SDR-33 data collector, I tie and calculate the positions of the found monuments as shown on the accompanying plat. The positions of the unfound corners were determined by proportional factors determined by measurement between found corners and record positions. The P.I. of the tangent lines were first proportioned between found monuments. The tangents between points of curve and P.I.'s or points of curve and found monuments were proportioned to allow for the proper positioning of the curve along the overall tangent. The delta's were held tangent and the radius fit to the proportioned positions.

Basis of Bearing is NAD-83 True North derived by global positioning satellite observations.

Surveyed by: Farber & Sons, Inc.
Farber Surveying
908 East Jackson Street
Medford, Oregon 97504

Date: September 6, 1995

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Herbert A. Farber

OREGON
JULY 26, 1985
HERBERT A. FARBER
2189

Expires 12/31/95

