



MAP OF SURVEY

LOCATED IN THE NORTHWEST QUARTER OF SECTION 29, TOWNSHIP 38 SOUTH, RANGE 3 WEST OF THE WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON FOR

MAYA LINDSAY

LEGEND:

- S/N INDICATES SURVEY NUMBER ON FILE AT THE JACKSON COUNTY SURVEYOR'S OFFICE, OREGON.
 BASIS OF BEARING IS THE EAST LINE OF THE NORTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 29 PER S/N 3894 AS SHOWN HEREON.
- SET 5/8 BY 24 INCH IRON PIN WITH YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
 - FOUND 5/8 INCH IRON PIN MONUMENT PER S/N 3824.
 - FOUND 5/8 INCH IRON PIN MONUMENT PER S/N 3894.
 - ⊗ FOUND 5/8 INCH IRON PIN MONUMENT PER S/N 4006.
 - ⊗ FOUND 5/8 INCH IRON PIN MONUMENT PER S/N 5702.
 - [()] INDICATES RECORD DATA PER S/N 3824.
 - [()] INDICATES RECORD DATA PER S/N 3894.
 - [()] INDICATES RECORD DATA PER S/N 4006.
 - [()] INDICATES RECORD DATA PER S/N 5702.

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: TO SURVEY AND MONUMENT THAT TRACT DESCRIBED IN INSTRUMENT No. 89-14169 OF THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.

PROCEDURE: UTILIZING A SOKKIA SET 4 TOTAL STATION AND A SOKKIA SDR 33 DATA COLLECTOR, I TIE IN A CLOSED TRAVERSE THE CONTROLLING MONUMENTS AND SET THE ADDITIONAL MONUMENTS AS SHOWN AND DESCRIBED HEREON. THE MONUMENTS SET ALONG THE SECTIONAL SUBDIVISION PER SURVEY No. 3894 WERE ACCEPTED AS BEING CORRECT AFTER CALCULATING THE RECORD SECTIONAL SUBDIVISION OF SECTION 29 PER SURVEY No. 3424 AND COMPARING IT TO THE FOUND MONUMENTATION OF SURVEY No. 3894 WHICH REFERENCED ITSELF TO SAID SURVEY No. 3424. THE SOUTHWEST CORNER, ALONG STATE HIGHWAY 238, WAS SET AFTER A TYING THE CENTER LINE OF THE EXISTING ROAD WAY AND ALLOWING FOR A 60 FOOT RIGHT OF WAY. THE HIGHWAY AT THE SOUTHEAST CORNER IS SHOWN BY THE FOUND MONUMENTS PER S/N 3894. THE INTERVENING SOUTH BOUNDARY WAS NOT LOCATED.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Herbert A. Farber

OREGON
 JULY 26, 1985
 HERBERT A. FARBER
 2189

Expires 12/31/95

SURVEYED BY: FARBER SURVEYING P.O. BOX 5286 CENTRAL POINT, OREGON 97502		OFFICE: 908 EAST JACKSON ST. MEDFORD, OREGON 97504 PHONE: (503) 776-0846	
COMPUTED BY: FAF SCALE: 1 inch = 100 feet DATE: 2 NOV 1995		ROTATION: 0° ORIGIN: 9660.000 N 8990.000 E JOB No.: 0533-95	

96-10630

4:25 5.00
6.00

14718

AFFIDAVIT OF CORRECTION

I, Herbert A. Farber, a registered Professional Land Surveyor in the State of Oregon, having the surveyed the land mapped on Filed Survey No. 14718 in the County Surveyor's Office in Jackson County, Oregon, acknowledge the following drafting error in said map: The spelling of LINDSAY should be LINDSEY.

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JULY 26, 1985
HERBERT A. FARBER
2189

Prepared by: Farber Surveying
Farber and Sons, Inc.
908 East Jackson Street
Medford, Oregon 97504

RENEWAL DATE 12-31-97

Date: April 4, 1996

Subscribed and sworn to before me this 4th day of April, 1996

Lyndall M. Sellens
Notary Public

OFFICIAL SEAL
LYNDALL M. SELLENS
NOTARY PUBLIC - OREGON
COMMISSION NO. 014591
MY COMMISSION EXPIRES APR 12, 1996

Examined and approved April 4, 1996⁶

Robert Roberts
Jackson County Surveyor

Jackson County, Oregon
Recorded
OFFICIAL RECORDS

4:25 APR 04 1996 PM

Robert J. Roberts
County Clerk