

Charles H. Hurst  
Land Surveyor  
765 Sunrise Ave.  
Medford, Oregon

County Surveyor  
Jackson County Courthouse  
Medford, Oregon

Dear Sir:

Reference is made to the 1/4 section corner common to sections 3 and 4, T39S, R1W, W.M.

During the course of some line running in the area I had the occasion to run a random line north from the SW corner of 3 with staff compass and chain, declination set at 19 3/4 degrees east.

At 39.72 chains I placed a three inch squared stake from which:

a 22" Madrone bears N76E 123 links  
a 9" Madrone bears S88W 59 links  
according to the original survey record.

The Madrone bearing N76E is down and the one bearing S88W has split down the center with original faces decayed.

A search of the hole at the bottom of the fire scar on the latter disclosed evidences of very old axe work and inconclusive evidence of scribing on a very small piece of the original face.


Supplimentary evidence regarding or supporting the probability that these trees are original witness trees is the fact that very old blazes were found on several trees along the random line made at approximately the same time the original survey was made. In addition, blazes were picked up on the random line run east from the point so located.

In view of the foregoing, I nailed to these two trees yellow tin BLM bearing tree tags duly filled out and bearing my registration number.

There is no doubt that these trees represent the original BT's insofar as I am concerned, but since definite evidence was not located during the time available, I did not make additional references with appropriate scribing.

Mr. George Williams, who has purchased a portion of the N 1/2 of the S 1/2 of Section 3 was present and is a witness to the information listed above. Mr. Williams address is temporarily P.O. Box 21, Talent, Oregon.

Sincerely,



*Charles H. Hurst*

