


14897

- B.T. was not found.
- (14) CENTER WEST 1/16 CORNER SECTION 30
set a 5/8 by 30 inch iron pin monument with yellow plastic cap marked "FARBER PLS 2189", from which bears:
an 8 inch Douglas Fir S38°W, 6.0 feet
an 11 inch Douglas Fir S56 3/4°E, 3.0 feet
all bearing trees are scribed "CW 1/16 S 30 B T" with U.S.D.A. Forest Service bearing tree tags (series 54-3) affixed at chest height, facing monument and marked LS 2189. All B.T.'s measured to the center of the tree at ground level.
- (15) CORNER No.4 GOLD NOTE No.2 LODE
found 8 inch by 24 inch stone, exposed 7 inches with chisel marks in a rock collar and accessories per Mineral Survey No. 923.
- (16) CORNER No.3 GOLD NOTE EXTENSION LODE
found 6 inch by 10 inch stone, exposed 6 inches in a rock collar with chisel marks and accessories per Mineral Survey No. 923.

Surveyed by: Farber & Sons, Inc.
Farber Surveying
908 East Jackson Street
Medford, Oregon 97504

Date: March 21, 1996

faf\box\nar.doc



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Herbert A. Farber

OREGON
JULY 26, 1985
HERBERT A. FARBER
2189

RENEWAL DATE 12-31-97

14897

a 7 inch Douglas Fir S76 1/2°W, 17.0 feet
a 5 inch Douglas Fir S58 1/4°E, 4.0 feet all bearing
trees are scribed "CS 1/16 S 30 B T" with U.S.D.A.
Forest Service bearing tree tags (series 54-3) affixed
at chest height, facing monument and marked LS 2189. All
B.T.'s measured to the center of the tree at ground
level.

- (7) SOUTH QUARTER CORNER SECTION 30
found 2 1/2 inch Jackson County brass cap, exposed 0.3
feet, with accessories per Jackson County corner notes,
the original fir snag was not found.
- (8) SOUTHWEST CORNER SECTION 30
found 3 1/2 inch standard B.L.M. brass cap, exposed 0.5
feet in rock collar, with accessories per B.L.M. corner
notes.
- (9) SOUTH 1/16 CORNER SECTION 25 AND 30
found 3 1/2 inch standard B.L.M. brass cap, exposed 0.3
feet, with accessories per B.L.M. corner notes.
- (10) WEST QUARTER CORNER SECTION 30
found 3 1/2 inch standard brass cap, with corner
accessories per B.L.M. corner notes.
- (11) NORTH 1/16 CORNER SECTION 25 AND 30
set a 5/8 by 30 inch iron pin monument with yellow
plastic cap marked "FARBER PLS 2189", from which bears:
a 7 inch Douglas Fir N82 3/4°W, 9.6 feet
a 14 inch Douglas Fir N79°E, 42.7 feet
all bearing trees are scribed "N 1/16 S 30 B T" with
U.S.D.A. Forest Service bearing tree tags (series 54-3)
affixed at chest height, facing monument and marked LS
2189. All B.T.'s measured to center of the tree at
ground level.
- (12) NORTHWEST 1/16 CORNER SECTION 30
set a 5/8 by 30 inch iron pin monument with yellow
plastic cap marked "FARBER PLS 2189", from which bears:
a 6 inch Douglas Fir N27°W, 18.0 feet
a 7 inch Sugar Pine S72 1/4°E, 23.5 feet
all bearing trees are scribed "NW 1/16 S 30 B T" with
U.S.D.A. Forest Service bearing tree tags (series 54-3)
affixed at chest height, facing monument and marked LS
2189. All B.T.'s measured to the center of the tree at
ground level.
- (13) CORNER No.3 GOLD NOTE No.2 LODGE
found 12 inch by 14 inch stone, exposed 6 inches with
chisel marks in a mound of stone and fir snag B.T. with
scribbling visible per Mineral Survey No. 923, the Yew

14897

of said Mining Claim Records. The Lode Claims having been filed after the above mentioned grants and being subsequently surveyed in June of 1953 as Mineral Survey No. 923. Those survey monuments being recovered by this office during the course of this survey. It was found that the recovered monuments are encroaching on the original grants. The property lines were marked holding the original grants and the encroachment was noted as shown on the accompanying Plat.

CORNER DESCRIPTION AND ACCESSORY INFORMATION

- (1) NORTHWEST CORNER SECTION 30
found 3 1/2 inch standard B.L.M. brass cap, exposed 0.40 feet in rock collar, with accessories per B.L.M. corner notes, the Grand Fir and the fir snag were not found.
- (2) NORTH QUARTER CORNER SECTION 30
found 3 1/2 inch standard B.L.M. brass cap, exposed 0.4 feet in rock collar, with accessories per B.L.M. corner notes, the root hole and the fir snag were not found.
- (3) NORTHEAST CORNER SECTION 30
found 3 1/2 inch standard B.L.M. brass cap, exposed 0.5 feet in rock collar, with accessories per B.L.M. corner notes, the original Cedar was not found.
- (4) EAST QUARTER CORNER SECTION 30
found a 5/8 inch iron pin monument with yellow plastic cap marked "ARTMAN RLS 2268", exposed 0.25 feet, with accessories per S/N 12185.
- (5) CENTER QUARTER CORNER SECTION 30
set a 5/8 by 30 inch iron pin monument with yellow plastic cap marked "FARBER PLS 2189", from which bears:
a 6 inch Cedar S52 1/2°W, 35.0 feet
a 9 inch Cedar S5 3/4°W, 39.7 feet
a 7 inch Cedar S85 1/2°E, 31.8 feet
a 18 inch Douglas Fir N64 1/2°W, 30.5 feet
all bearing trees are scribed "C 1/4 S 30 B T" with U.S.D.A. Forest Service bearing tree tags (series 54-3) affixed at chest height, facing monument and marked LS 2189. All measurements to B.T.'s taken to the center of the tree at ground level.
- (6) CENTER SOUTH 1/16 CORNER SECTION 30
set a 5/8 by 30 inch iron pin monument with yellow plastic cap marked "FARBER PLS 2189", from which bears:

Survey No. 14897

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

Survey for: Boise Cascade Corporation
P.O. Box 100
Medford, Oregon 97501

Location: Located in the northeast, northwest and southwest quarters of Section 30, Township 33 South, Range 4 West of the Willamette Meridian, Jackson County, Oregon.

Purpose: To survey and monument and mark the property lines as shown on the accompanying Plat.

Procedure: Utilizing Trimble ST and SSi Global Positioning receivers and a Nikon AL-10 total station and Sokkia SDR33 data collector I tie the controlling monuments and subdivide the section as shown on the accompanying Plat. The Lot 1 and the northeast quarter of the northwest quarter of Section 30 was patented in 1909 to William H. Fisher as recorded in Volume 64, Page 347 of the Deed Records of Jackson County, Oregon. The west half of the northeast quarter, the southeast quarter of the northwest quarter and the northwest quarter of the southeast quarter of said Section 30 was patented in 1909 to James Brackett as recorded in Volume 64, Page 428 of said Deed Records. The Lot 4, the southeast quarter of the southwest quarter and the southwest quarter of the southeast quarter of said Section 30 was patented to William H. Sprangle in 1909 as recorded in Volume 54, Page 628 of said Deed Records. Notice of Lode Claim Location for Gold Note No.2 Mining Claim was recorded on the 1st of June, 1948 in Volume 49, Page 47 of the Mining Records of Jackson County, Oregon and the Gold Note Extension location certificate was filed on the 27th of April, 1936 in Volume 33, Page 624