

14938

MAP OF SURVEY (PROPERTY LINE ADJUSTMENT)

SURVEY BY:

CITY OF MEDFORD
SURVEY DIVISION
411 W 8TH ST.
MEDFORD, OR 97501

LOCATED IN:

NW 1/4 SECTION 21, T37S, R1W, W.M.
JACKSON COUNTY, OREGON

OCTOBER 23, 1995

SURVEY FOR:

CITY OF MEDFORD
PARKS DEPARTMENT
411 W 8TH ST
MEDFORD, OR. 97501

SURVEY NARRATIVE TO COMPLY WITH 209.250, OREGON REVISED STATUTES

PURPOSE: TO MONUMENT A PROPOSED PROPERTY LINE PURSUANT TO ORS 92.060 (9).
PROCEDURE: THE FOUND DEED CORNERS (3/4" IRON PIPES) WERE HELD FOR THE LINE COMMON TO V.568 P.472; V.590P.340 AND V.420P.180. THESE PIPES ALIGNED WELL WITH A PIN SET ON SN 11954 FOR BOUNDARY LINE AGREEMENT OR 89-24652. THE WEST LINE OF V.568 P.472 MAKES A REFERENCE TO LOT 6 OF PIERCE SUBDIVISION. SINCE THIS IS INDETERMINATE, A WITNESS CORNER WAS SET NEAR THE WEST END OF THIS PROPERTY LINE ADJUSTMENT. THE NORTHERLY LINE OF SECTION 21 WAS HELD FOR THE CENTERLINE OF LONE PINE ROAD.

LEGEND

- FOUND 3/4" IRON PIPE, DEED CORNER
 - FOUND 5/8" IRON PIN WITH PLASTIC CAP MARKED: "BOYDEN RLS 281", SN 11954.
 - ▣ FOUND 5/8" IRON PIN MARKED: "R. BATH LS 1069", SN 10301
 - FOUND BRASS CAP IN CONCRETE, FLUSH
 - ⊙ FOUND BRASS CAP IN MONUMENT CASE
 - SET 5/8" BY 24" IRON PIN WITH PLASTIC CAP MARKED: "CITY OF MEDFORD"
- SN = SURVEY NUMBER
OR = JACKSON COUNTY OFFICIAL RECORDS

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Paul D. Lewis
OREGON
JULY 14, 1978
PAUL D. LEWIS
1624

EXPIRATION DATE 12-31-96

