

REPORT TO PERPETUATE THE ORIGINAL CORNER EVIDENCE FOUND AT
THE QUARTER CORNER COMMON TO SECTIONS 20 and 29, TOWNSHIP
37 SOUTH, RANGE 1 EAST

Found both original witness trees down with scribe marks
legible.

Set a 1"x36" iron pipe 36" in the ground from which:

The stump remains (which stump fits the diameter
of the 16" Black Oak tree lying downhill and
plainly scribed 1/4 &) bears South 40° East, 21.8 feet;

The snag of the Yellow pine is lying downhill from
where the original Northwest witness tree would have
stood, but no stump remains could be found.

Scribe an 8" Fir "CS-BT" which bears South 41° W, 4.4 feet;

Scribe a 10" Fir "CS-BT" which bears South 47½° East 26.0 feet;

Var. 20° E.

July 22, 1960

Mark E. Boyden
F.A. Roberts
O. Blankenship

NOTE: Mr. Schmidt, an old time resident feels this corner
should move 8 - 10 feet East and 2 - 3 feet North. There
is no definite evidence on the ground to substantiate
this ascertainment, but transit lines should be run into this
corner from adjoining corners before this corner is officially
accepted.

REGISTERED
OREGON
LAND SURVEYOR

Mark E. Boyden
NOVEMBER 9, 1951
MARK E. BOYDEN
281