



LEGEND

- ✚ SECTION CORNER FOUND
- ⊕ 1/4 SECTION CORNERS FOUND
- SET 2" IRON PIPE FOR 1/4 CORNERS.

J.A. FARREN

FIR MILLING & PLANING CO

S 1/2 SW 1/4 SECTION 24

BEARINGS BY SOLAR OBSERVATION

FD 2 B.T.'S, SET 2" I. PIPE & BLAZED 2 B.T.'S FOR SECTION CORNER

SET 2" I. PIPE & BLAZED 2 B.T.'S FOR W 1/2 CORNER

FD. B.T., SET 2" I. PIPE & BLAZED 1 B.T. FOR 24 1/4 CORNER

FIR MILLING & PLANING CO

W 1/2 NW 1/4 SECTION 25

SURVEY FOR
 FIR MILLING AND PLANING CO.
 SITUATED IN

SECTIONS 24 and 25, T40S, R2E, W.M.
 JACKSON COUNTY, OREGON

P. LOVEJOY, REGISTERED LAND SURVEYOR
 MEDFORD, OREGON JULY 28, 1960

SCALE: 1" = 600'

REGISTERED
OREGON
 LAND SURVEYOR

Leland P. Lovejoy

NOVEMBER 8, 1942
 LELAND P. LOVEJOY
 262

RECEIVED
 JACKSON COUNTY
 AUG 1 1960
 ENGINEER-SURVEYOR

Survey Narrative to Comply with Section 87-3301947 Oregon State Laws

Survey for: Fir Milling & Planing Co.
505 Tolman Creek Road
Ashland, Oregon

Purpose of Survey: To determine property boundaries.

Survey Location: Sections 24 and 25, Township 40 South,
Range 2 East, Willamette Meridian,
Jackson County, Oregon

Survey Procedure: Found original bearing trees at section
and quarter corners, as shown on map,
and, from original field notes, set
1 3/4" and 2" iron and steel pipe to
perpetuate these corners. Established
1/16 corners mid-point between section
and quarter corners and set 2" iron pipe.

Leland P. Lovejoy
Registered Land Surveyor
Work completed July 21, 1960

