

MAP OF SURVEY

Located in the Northeast and Southeast One-quarters of Section 1, Township 37 South, Range 4 West, Willamette Meridian, Jackson County, Oregon

April 24, 1997

SURVEYED FOR:

Gilbert and Helen Hice
2221 Footh Creek Road
Gold Hill, Oregon 97525

SURVEYED BY:

Neathamer Surveying, Inc.
1160 North Keene Way Drive
Medford, Oregon 97504
Phone: 541-752-2069
FAX: 541-752-1382

LEGEND:

- Indicates found Brass Capped monument per Survey Number 15313, and as noted.
- Indicates a found 5/8 inch steel pin with yellow plastic cap marked "NEATHAMER PLS 2675", SN 15313.
- Indicates a set 5/8" by 30 inch steel pin with yellow plastic cap marked "NEATHAMER PLS 2675", top set flush with the ground.
- Indicates computed position.
- [] Indicates record data per Dependent Resurvey performed by the Bureau of Land Management in 1985 and identified as group numbers 1251 and 1289. Distances from said survey are in chains.
- () Indicates record data per Survey Number 15313.
- GLO Indicates record data from the General Land Office Surveys. GLO distances measurements are in chains.
- SN Indicates a survey filed by number at the Jackson County Surveyors Office, Jackson County, Oregon.
- All Bearing Tree ties are to the center of the tree.

PURPOSE:

To perform a field survey and monument Clients' boundary corners based on Document Number 69-07367, Official Records of Jackson County, Oregon, as provided by Clients'.

PROCEDURE:

Utilizing a Nikon DTM 420 Total Station, a closed loop field traverse was performed encompassing the quarter and sixteenth corners depicted hereon.

Based on said traverse and Survey Number 15313, previously performed by this office, the Northeast One-quarter of Section one was mathematically subdivided into quarters. Pursuant to said Document Number 69-07367, Clients' boundary lines were computed and the corner positions monumented.

BASIS OF BEARINGS

The easterly line of Section One pursuant to a Dependent Resurvey performed by the Bureau of Land Management in 1985 and identified as group numbers 1251 and 1289.

REGISTERED PROFESSIONAL LAND SURVEYOR

Robert V. Neathamer

OREGON
JULY 19, 1994
ROBERT V. NEATHAMER
02675LS

Renewal Date: 12/31/98

