



**LEGEND**

- FOUND B.L.M. BRASS CAP PER B.L.M. BOOK, ERA 1956.
  - ( ) RECORD BEARING/DISTANCE PER B.L.M. 1956 SURVEY.
- BEARINGS BASED UPON SOLAR OBSERVATION.

NOTE: NO MONUMENTS SET ON THIS SURVEY.

**SURVEY NARRATIVE**

**PURPOSE:** To survey and mark the East line of the NW 1/4 of Section 19 as requested by my client; to mark said line, by blazing and painting with flo-red paint with Boise aluminum tags, as shown on accompanying map.

**BASIS OF BEARING:** Bearings based upon solar observation.

**PROCEDURE:** I tied North, South and C 1/4 of Section 19, along with the CN 1/16 as set by the B.L.M. in 1956. Running from the North 1/4 of Section 19 to the CN 1/16 to the C 1/4 corner, I found that the distances did not match record between the existing corners. After discussing the problem with my client it was decided to tie the South 1/4 corner in order to mark the East line of the NW 1/4 correctly. Since Boise owns the West half of Section 19 and B.L.M. has the East half it was decided not to locate the true position of the C 1/4 corner at this time. The East line of the NW 1/4 was marked on the true North-South centerline of Section 19, holding the North and South 1/4 corners.

36\_3E\_19 NW 1/4

**\*\* RECEIVED \*\***  
Date 6-17-97 By RF  
This survey consists of:  
1 sheet(s) Map  
0 page(s) Narrative  
JACKSON COUNTY SURVEYOR

**REGISTERED PROFESSIONAL LAND SURVEYOR**  
*Richard G. Templin*  
OREGON  
JULY 26, 1988  
**RICHARD G. TEMPLIN**  
2359  
My Certificate Expires Dec. 31, 1997

**RICHARD TEMPLIN LAND SURVEYING**  
100 POORMAN CREEK RD. 899-2032 / 474-7720 JACKSONVILLE, OREGON

**MAP OF SURVEY**  
LOCATED IN  
THE NW 1/4 OF SECTION 19, T. 36S., R. 3E., W.M.,  
JACKSON COUNTY, OREGON  
SURVEYED FOR: BOISE CASCADE CORP. DATE: JUNE 15, 1997  
P.O. BOX 100  
MEDFORD, OR. 97501