

SURVEY NO. 15417

**Certified Record of Land Corner Monumentation  
to Comply With Paragraph 209.250, O.R.S.**

**History of Original Establishment:**

The original corner point for the Standard one-quarter Section Corner for Section 31 only, Township 39 South, Range 1 West, Willamette Meridian, Oregon, was established by Rufus S. Moore, per Contract No. 475 in 1883. This corner was remonumented from evidence by the Bureau of Land Management in 1972. Richard Templin, RLS 1354 visited this corner in 1980.

**Description of Corner Evidence Found:**

At the corner point, I found a standard Bureau of Land Management 2 1/2-inch diam. steel post protruding 4 inches above ground with a 3-inch diam. brass cap attached, marked:

U.S. DEPT. OF INTERIOR

T39S R1W  
1/4 . S 31

1972  
CADASTRAL SURVEY

and the following accessories:

A 30-inch diameter Douglas Fir bears N.53°10' W., 40.9 Ft. distance, with a partially healed blaze. (R. Templin Record N.52°49' W., 40.79 Ft.).

A 36-inch diameter Ponderosa Pine stump with a dead and down tree alongside, bears N.43°54'E., 24.1 ft. distance, with scribing visible on an opened blaze. (R. Templin Record N.43°25'E., 24.0 ft.) Also from which, the North one-quarter corner for Section 6 only, Township 40 South, Range 1 West, W.M., bears S.89°49'53"W., 142.32 ft.) This is the basis of bearing for this re-establishment, as per Templin 1980 survey.

**Description of Accessories Established to Perpetuate the Original Corner Position:**

I mark the following new accessory:

A 13-inch diameter Douglas Fir bears N.75°56'E., 33.5 Ft. distance, marked "T39SR1WS31BT," with a brass washer stamped LS2332 attached to base of tree.

**Basis of Bearing: Solar Observation**

**Date: May 12, 1997**

Stephan L. Barott  
Registered Professional Land Surveyor  
Oregon Certificate No. 2332  
Expires 12/31/97

