

SURVEY NO. **15418**

**Certified Record of Land Corner Monumentation
to Comply With Paragraph 209.250, O.R.S.**

History of Original Establishment:

The original corner point for the Closing Section Corner for Sections 2 and 3, Township 31 South, Range 4 East, Willamette Meridian, Oregon, was established by N. Price under Group 176 dated March 17, 1936.

Description of Corner Evidence Found:

At the corner point, I found a 1-inch diam. steel post protruding 10 inches above ground with a 2 1/2-inch diam. brass cap attached, marked:

GENERAL LAND OFFICE SURVEY
30S R4E

S3 | S2
|
T31S R4E
C C
1937

and the following accessories:

A 9-inch diameter Lodgepole Pine bears S.27°00' W., 29.2 Ft. distance, with scribing "T31SR4ES3CCBT" visible on a partially healed blaze. (Record S.27 1/4° W., 45 lks. = 29.7 Ft.).

A 7-inch diameter Lodgepole Pine stump with a dead and down tree alongside, bears S.22°28'E., 40.0 ft. distance, with scribing "CCBT" visible on stump. (Record 61 lks. = 40.3 Ft)

Also from which, the corner for Sections 34 and 35, Township 30 South, Range 4 East, W.M., bears West, 298.56 Ft. distance. (Record 4.52 CH = 298.32 Ft.). **This is the basis of bearing for this re-establishment.**

Description of Accessories Established to Perpetuate the Original Corner Position:

I mark the following new accessory:

A 7-inch diameter Lodgepole Pine bears S.50°48'E., 10.4 Ft. distance, marked "T31SR4ES2CCBT," with a brass washer stamped LS2332 attached to base of tree.

Basis of Bearing: Solar Observation

Date: June 23, 1997

Stephan L. Barott
Registered Professional Land Surveyor
Oregon Certificate No. 2332
Expires 12/31/97

