


CITY OF ASHLAND



CITY HALL

ASHLAND, OREGON 97520
telephone (code 503) 482-3211

Survey No. 15476

May 5, 1997

**** RECEIVED ****
Date 5-12-97 By BF
This survey Consists of:
0 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

JACKSON COUNTY SURVEYOR
Court House
Medford, Oregon 97501

Re: Replacement of a street intersection monument, now of record.

Dear Roger:

SURVEY FOR: City of Ashland
City Hall
Ashland, Oregon 97520

LOCATION: Situated in the Southwest quarter of Section 5, Township 39 South, Range 1 East of the Willamette Base and Meridian, Jackson County, Oregon.

PURPOSE: To re-monument the centerline intersection of Wimer Street and Wrights Creek Drive as set forth on that filed Survey No. 10634 in the office of the Jackson County Surveyor. The monument will now serve, in addition to a street centerline intersection point, a Global Positioning System (GPS) reference point as set forth hereinbelow.

PROCEDURE:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Everett L. Swain

OREGON
JULY 8, 1988
EVERETT L. SWAIN
750

Renewal Date: 6/30/98

Found a 30 inch long by 5/8 inch diameter Iron Rod with 1.5 inch diameter Aluminum Cap marked "LS 759, 1986" with a drill hole therein and flush with the street surface. This monument was referenced with four (4) strad PK Nails and then removed. In its place a standard street centerline monument case was installed and a 30 inch long by 1 inch diameter iron pipe was driven to a depth of 33 inches. Placed a 3 inch diameter bronze cap in top of said iron pipe and marked the bronze cap as follows: CITY OF ASHLAND, GPS 525, 1997, SURVEY MARKER, with a drill hole at the intersection of the previously set strad PK Nails.

Everett L Swain, P.L.S.
Assistant City Surveyor
City Hall
Ashland, Oregon 97520

ref: CACONT97.doc