

MAP OF SURVEY
Of Lot 6, Block 71 of the ORIGINAL TOWN OF MEDFORD, located in the S.W. 1/4 of Sec. 30, T.37 S., R.1 W., W.M. Jackson County, Oregon

SURVEY FOR:

KAS & ASSOCIATES
 304 SOUTH HOLLY STREET
 MEDFORD, OR 97501

SURVEY BY:

L.J. FRIAR & ASSOCIATES, P.C.
 CONSULTING LAND SURVEYORS
 816 WEST EIGHTH STREET
 MEDFORD, OREGON 97501
 PHONE: (541) 772-2782

LEGEND:

- - CENTERLINE INTERSECTION POINT ESTABLISHED FROM CITY OF MEDFORD RP'S.
- - SET 5/8" X 24" IRON PIN W/ PLASTIC CAP MKD. L.J. FRIAR & ASSOC.
- ⊗ - SET BRASS TAG MKD. LS2234 IN LEAD PLUG IN SIDEWALK.
- () - PLAT RECORD DATA. RS - RECORDED SURVEY #.

BASIS OF BEARINGS: CENTERLINE OF SOUTH HOLLY STREET PER RS8844.

DATE: JULY 30, 1997 **SCALE:** 1" = 30' **UNIT OF MEASUREMENT - FEET**

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: TO SURVEY AND MONUMENT THE CORNERS OF THE CLIENTS TAXLOT IN CONJUNCTION WITH A TOPOGRAPHIC SURVEY.

PROCEDURE: MADE TIES TO CITY OF MEDFORD RP'S AT EACH INTERSECTION AS SHOWN HEREON. CALCULATED THE INTERSECTION OF WEST 10TH AND SOUTH IVY BY SPLITTING THE DISTANCE FROM THE INTERSECTIONS UP AND DOWN WEST 10TH STREET. USED PROPORTIONATE METHOD TO COMPUTE THE LOT CORNERS AND SET MONUMENTS AS SHOWN HEREON.

**** RECEIVED ****
 Date 11-21-97 By [Signature]
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
JACKSON COUNTY SURVEYOR

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
[Signature]
 OREGON
 JULY 17, 1986
 JAMES E. HIBBS
 2234
 Renewal Date 6-30-99

