

PROPERTY SURVEY

FOUND: IRON PIPE WITH 2 1/2"
BRASS CAP AND ACCESSORIES
AS ESTABLISHED IN 1982.
(SURVEY # 9500)

SECTION 27, T. 32 S., R. 2 E., W.M.
JACKSON COUNTY, OREGON
APRIL, 1998

15737

SURVEY BY:
TONY HOSTETTER
540 EVERETT ST.
COOS BAY, OR 97420

SURVEY FOR:
BOISE CASCADE CORPORATION
PO BOX 100
MEDFORD, OREGON 97501

NARRATIVE:

THIS SURVEY WAS PERFORMED IN ORDER TO DETERMINE PROPERTY BOUNDARIES AS SHOWN.

PROPERTY LINES BETWEEN FOUND MONUMENTS WERE TRAVERSED USING A NIKON DTM-730 TOTAL STATION. BASIS OF BEARING PROVIDED BY SURVEY NO. 9500.

OFFSETS TO TRUE LINE WERE CALCULATED, LINE WAS MARKED BY BLUE FLAGGING AND BOTH SIDES OF LINE WERE BLAZED AND PAINTED. ALUMINUM TAGS PLACED INTERMITTENTLY ALONG LINE WERE NAILED ON ROOT COLLARS BELOW BLAZES (ONLY PLACED ON TREES WITHIN 1 FOOT OF TRUE LINE).

1/4 CORNER
SECTION 27
ONLY

FOUND: BRASS CAP AND ACCESSORIES
AS DESCRIBED IN 1982.
(SURVEY NO. 9500)

(SURVEY NO. 10253)
(N 0°00'45" E, 1334.60)

N 0°03'11" W
1334.56

LEGEND:

CORNER FOUND: 


CORNER SET: 


LINE BLAZED 

RECORD SURVEY 



SCALE 1" = 200'

** RECEIVED **
Date 5-15-98 By 
This survey consists of:
1 sheet(s) Map
0 page(s) Narrative
JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JAN 10, 1982
TONY HOSTETTER
1975
EXPIRES: 6/30/99

S 1/16
FOUND: 2" BRASS CAP AND
ACCESSORIES AS SET IN 1985
(SURVEY NO. 10253)

URLICK2.GCD 5/13/98

15737