

MAP OF SURVEY

OF
NORTH PHOENIX ROAD
BETWEEN BARNETT ROAD AND CHERRY LANE
LOCATED IN
THE SOUTHWEST QUARTER OF SECTION 27,
TOWNSHIP 37 SOUTH, RANGE 1 WEST,
WILLAMETTE MERIDIAN
CITY OF MEDFORD, JACKSON COUNTY,
OREGON

COUNTRY CLUB
VILLAGE ESTATES
SOUTH VILLAGE
A PLANNED COMMUNITY DEVELOPMENT

ROCKWOOD
SUBDIVISION

GREYSTONE
ESTATES
SUBDIVISION

MEADOW PARK
SUBDIVISION
UNIT NO. 1

SHAMROCK
DRIVE
BRANNON
HEIGHTS
SUBDIVISION

MICHAEL PARK
DRIVE
MICHAEL PARK
SUBDIVISION
A PLANNED UNIT DEVELOPMENT

BARNETT ROAD

STERLING POINTE
COURT
DRIVE

FOUND 3" DIAMETER DISC
W/PUNCH MARK & SLASHES IN
CONCRETE STAMPED "JACKSON
COUNTY 1980 T37S R1W DLC 58
B-163" (2" DOWN)

FOUND 2" DIAMETER BRASS DISC
W/PUNCH MARK IN CONCRETE
STAMPED "LS 1913" (FLUSH)

FOUND 2-1/2" DIAMETER BRASS
DISC W/PUNCH MARK IN CONCRETE
STAMPED "LS 1913" (FLUSH)

FOUND 2" DIAMETER BRASS DISC
W/PUNCH MARK IN CONCRETE
STAMPED "LS 1913" (FLUSH)

MONUMENT LOCATION
PER RECORD DISTANCE
SOUTH FROM D.L.C.
PER GREYSTONE ESTATES
SUBDIVISION

FOUND 2-1/2" DIAMETER BRASS
DISC W/PUNCH MARK IN MONUMENT
CASE STAMPED "LS 1913"
(4" DOWN)

FOUND 2" DIAMETER BRASS DISC
W/PUNCH MARK IN CONCRETE
STAMPED "LS 1640" (FLUSH)

FOUND 2-1/2" DIAMETER BRASS
DISC W/PUNCH MARK & SLASHES
IN MONUMENT CASE STAMPED
"T37S R1W DLC 58/59 1994"
(2" DOWN)

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

SURVEY FOR: CITY OF MEDFORD
411 WEST EIGHTH STREET
MEDFORD, OR 97501

SURVEY BY: CITY OF MEDFORD
LAND SURVEY DIVISION
411 WEST EIGHTH STREET
MEDFORD, OR 97501

DATE: JULY 1998

PURPOSE: TO REPLACE MONUMENTS DESTROYED DURING STREET IMPROVEMENTS
ON NORTH PHOENIX ROAD.

PROCEDURE: MONUMENTS WERE SET FROM REFERENCE POINT INFORMATION
CITY OF MEDFORD FIELD BOOK NUMBER 1719

BASIS OF BEARINGS: NONE

EQUIPMENT: WILD T-1000 TOTAL STATION

LEGEND

- SET 2-1/2" DIAMETER BRASS DISC W/DRILL HOLE STAMPED "CITY OF MEDFORD SURVEYOR" IN A 2" DIAMETER IRON PIPE IN MONUMENT CASE
- ⊗ SET 5/8"x30" IRON PIN W/PLASTIC CAP STAMPED "MEDFORD CITY SURVEYOR"
- SET 5/8"x24" IRON PIN W/PLASTIC CAP STAMPED "MEDFORD CITY SURVEYOR"
- FOUND 5/8" IRON PIN W/PLASTIC CAP STAMPED "D. MCMAHAN LS 1913" PER "MEADOW PARK SUBDIVISION, UNIT NO. 1"
- ⊙ FOUND 2-1/2" DIAMETER BRASS DISC W/PUNCH MARK STAMPED "LS 1913" IN MONUMENT CASE, UNLESS NOTED OTHERWISE

NOTES

ALL OFFSET DISTANCES ARE AT RIGHT ANGLES TO THE MONUMENT LINE OF NORTH PHOENIX ROAD UNLESS NOTED OTHERWISE.

** RECEIVED **

Date 9-1-98 By PL

This survey consists of:
1 sheet(s) Map
0 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Paul D. Lewis

OREGON
JULY 14, 1978
PAUL D. LEWIS
1644

EXPIRATION DATE
DECEMBER 31, 1998

SCALE: 1" = 100'

