



**MAP OF SURVEY**  
of  
Lot 2, Block 71 of the ORIGINAL TOWN OF MEDFORD  
located in  
SOUTHWEST ONE QUARTER OF SECTION 30  
TOWNSHIP 37 SOUTH, RANGE 1 WEST  
WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON  
for  
**NED & HELEN SOSO**  
119 Mountain Ranch Drive  
Fairfield Bay, Arkansas 72088

**LEGEND**

- ⊕ = 2 1/2" BRASS CAP - STREET CENTERLINE MONUMENT (RECOVERED)
- = 5/8" IRON PIN MONUMENT, W/ PLASTIC CAP MKD. L.J. FRIAR & ASSOC. (RECOVERED)
- = 5/8" x 24" IRON PIN MONUMENT w/ YELLOW PLASTIC CAP MARKED "FARBER PLS 2189" (ESTABLISHED)
- ⊕ = CITY OF MEDFORD R.P. (.32 OR .38 CALIBER SHELL CASING, AS SHOWN) PER CITY OF MEDFORD FIELD BOOKS (AS NOTED)
- ⊙ = BRASS RIVET IN CONCRETE IN MONUMENT CASE (RECOVERED)
- S/N = RECORD FILED SURVEY NUMBER

- BASIS OF BEARING IS TRUE NORTH, NAD 83 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.  
- MONUMENTS DESCRIBED IN LEGEND ARE TYPICAL UNLESS OTHERWISE NOTED ON PLAT.  
- RECORD SURVEY DATA IS SHOWN IN PARENTHESIS ADJACENT TO MEASURED SURVEY DATA WHERE APPLICABLE.

**\*\* RECEIVED \*\***  
Date 3-23-99 By [Signature]  
This survey consists of:  
1 sheet(s) Map  
0 page(s) Narrative  
**JACKSON COUNTY SURVEYOR**

**REGISTERED PROFESSIONAL LAND SURVEYOR**  
[Signature]  
**OREGON**  
JULY 26, 1985  
HERBERT A. FARBER  
2189  
RENEWAL DATE 12-31-99

**SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250**

PURPOSE: TO SURVEY AND MONUMENT PROPERTY LINES AS REQUESTED.

PROCEDURE: UTILIZING GLOBAL POSITIONING SATELLITES I TIE THE MONUMENTS AND R.P.'S AS SHOWN HEREON. CALCULATED THE INTERSECTION OF WEST 11TH AND "J", WEST 11TH AND IVY, FROM R.P. TIES. THEN USED PROPORTIONATE METHOD TO COMPUTE THE LOT CORNERS AND SET MONUMENTS AS SHOWN HEREON.

Surveyed by:  
**FARBER & SONS, INC.**  
dba FARBER SURVEYING  
(541) 776-0846

OFFICE LOCATION: 120 MISTLETOE MEDFORD, OREGON 97501  
MAILING ADDRESS: P.O. BOX 5286 CENTRAL POINT, OREGON 97502

SCALE: 1" = 30'  
DATE: MARCH 15, 1999  
JOB NO. 0809-98  
DRAWING FILE: JOBS\MISTLETOE\SOSA-MOS.FLX