

MAP OF SURVEY

LOCATED IN
THE SOUTHWEST QUARTER OF SECTION 7
TOWNSHIP 37 SOUTH, RANGE 1 WEST,
WILLAMETTE MERIDIAN,
CITY OF MEDFORD, JACKSON COUNTY, OREGON

SURVEY FOR:
CITY OF MEDFORD
ENGINEERING DIVISION
411 WEST EIGHTH STREET
MEDFORD, OREGON 97501

SURVEY BY:
CITY OF MEDFORD
LAND SURVEY DIVISION
411 WEST EIGHTH STREET
MEDFORD, OREGON 97501

FEBRUARY 1999

BRASS CAP IN
CONCRETE
QUARTER CORNER
12 | 7

SCALE: 1" = 100'

CURVE	DELTA	RADIUS	ARC	TANGENT	BEARING	CHORD
C1	09°39'30"	500.00	84.28	42.24	S 84°58'15" E	84.19
C2	34°35'00"	500.00	301.80	155.65	S 62°51'00" E	297.24
C3	45°34'16"	200.00	159.07	84.01	S 22°46'22" E	154.91
C4	38°31'30"	250.00	168.10	87.37	S 09°24'15" E	164.95
C5	18°20'00"	500.00	159.99	80.68	N 19°30'00" W	159.31

BIDDLE ROAD

LAWNSDALE ROAD

TERMINAL SPUR ROAD

BULLOCK ROAD

**** RECEIVED ****

Date 5-6-99 By CC

This survey consists of:
 sheet(s) Map
 page(s) Narrative

JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR

Paul D. Lewis

OREGON
JULY 14, 1978
PAUL D. LEWIS
1644
EXPIRES DECEMBER 31, 2000

LEGEND

- ⊙ SET 2-1/2 DIAMETER BRASS DISC W/DRILL HOLE STAMPED "CITY OF MEDFORD SURVEYOR" IN A 2" DIAMETER IRON PIPE IN MONUMENT CASE.
- FOUND MONUMENT AS NOTED.

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

DATE: APRIL 1999

PURPOSE: TO MONUMENT THE CENTERLINE OF A 70 FOOT WIDE RIGHT-OF-WAY TO BE DEEDED FROM JACKSON COUNTY TO THE CITY OF MEDFORD.

PROCEDURE: THE WEST LINE OF SECTION 7 AND THE EAST LINE OF D.L.C. NUMBER 38 WERE TIED TOGETHER WITH THE STREET IMPROVEMENTS ALONG LAWNSDALE, TERMINAL SPUR AND BULLOCK ROAD. FROM THIS INFORMATION A LOCATION WAS DETERMINED AND MONUMENTED AS SHOWN.

BASIS OF BEARINGS: SURVEY NUMBER 9132

EQUIPMENT: WILD T-1000 TOTAL STATION

BRASS CAP IN MONUMENT CASE SECTION CORNER 12 | 7

13 | 18

T.37S. R.1W. 7