



map of Survey

Donation Land Claim No.48 in the Northeast One/Quarter of Section 11 Township 39 South of Range 1 East of the Willamette Base and Meridian,

JACKSON COUNTY OREGON

Sidney E. Ainsworth

2939 Deer Trail Lane Medford, Oregon 97501

Narrative of Survey

Purpose: to monument a bridge site

Procedure: From a previously established survey network the shown monuments were set. Elevations were derived trigonometrically from F.A.A. Survey monuments (sleeved stainless steel rods in concrete), the primary vertical control monument was "Station FAA S03 A" at 1878.00 feet above mean sea level(1929 datum). It is located between the taxiway and the runway of Ashland Municipal Airport. The monuments established in filed survey 14207 were apparently disturbed by equipment that was clearing blackberries & brush. These were reset and additional Property Line monuments were set South of Bear Creek.

the Southeast corner of Donation Land Claim No.44 being a 2.5" Jackson County bronze disk which bears N 74°19'23"W 1552.26'

note:

the East line of Donation Land Claim No.44 bears: N 00°07'15"E 2647.71' (N00°04'30"E 2647.83' f.s.8466) (N00°07'15"E 2648.48' f.s.2279)

SURVEYOR

STEWART LAND SURVEYS 6370 Highway 66 Ashland, Oregon 97520

July 1, 1999

SCALE: 1" = 80' BASIS OF BEARING:

phone (541) 488-2831 filed survey No.2279

at the East Line of Donation Land Claim No.44

\*\* RECEIVED \*\*  
 Date 8-3-99 By [Signature]  
 This survey consists of:  
 1 sheet(s) Map  
 0 page(s) Narrative  
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR  
 Martin C. Stewart

OREGON JULY 15, 1985 MARTIN C. STEWART 2057

Surveyor's Registration Renewal Date is June 30, 2000

Legend

- = found: survey monument as noted
- = set: 5/8" X 32" iron rod with a yellow plastic cap marked: "STEWART LS 2057"
- = surveyed boundary line
- f.s. = filed survey found in the Jackson County Surveyor's Office
- D.R.J.Co. = Deed Records of Jackson County, Oregon
- O.R.J.Co. = Official Records of Jackson County, Oregon