

MAP OF SURVEY

LOCATED in the SW 1/4 of Section 7, T. 35 S., R. 1 E., W.M. in Jackson County, Oregon.

September 11, 1999

SURVEYED FOR: *NANCY CASSLEY*
3444 BUTTE FALLS HWY.
EAGLE POINT, OREGON

SURVEYED BY: *DAVID EDWARDS LAND SURVEYING*
P.O. BOX 361
OAKLAND, OREGON 97462
PHONE: (541) 459-0512

REGISTERED
PROFESSIONAL
LAND SURVEYOR
David G. Edwards
OREGON
JULY 24, 1988
DAVID A. EDWARDS
2339
EXPIRES 12/31/99

**** RECEIVED ****
Date 9-29-99 By DE
This survey consists of:
1 sheet(s) Map
0 page(s) Narrative
JACKSON COUNTY
SURVEYOR

LEGEND

- ⊙ INDICATES JACKSON COUNTY SURVEYOR BRASS CAP FOUND.
- INDICATES 5/8" X 30" STEEL PIN W/RED PLASTIC CAP MKD. "D.A. EDWARDS-LS 2339" SET.
- () DENOTES RECORD DATA PER SURVEY NO. 11271 UNLESS NOTED OTHERWISE.
- DOC. NO. = OFFICIAL RECORDS FOR JACKSON COUNTY.
- SCALE: 1" = 200'
- BASIS OF BEARINGS: SURVEY NUMBER 11271 AS SHOWN.
- INDICATES 5/8" DIAM. REBAR R/W MON. BY JACK. CO. DEPT. OF PUBLIC WORKS FOUND.

NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO MONUMENT AND FLAG THE BOUNDARIES OF THAT TRACT OF LAND DESCRIBED AS PARCEL 1 IN DOCUMENT NO. 89-25886 AND A PORTION OF THE SOUTH LINE OF SECTION 7. THE LINES SURVEYED ARE SHOWN AS BOLD HEREON, EXCEPT FOR THE HIGHWAY RIGHT OF WAY. DOCUMENT NO. 89-25886 IS CONTROLLED BY THE EAST AND SOUTH LINES OF THE SW 1/4 OF THE SW 1/4 OF SECTION 7. CONTROLLING MONUMENTS AROUND SECTION 7 WERE TIED INTO AND THE SUBDIVISION OF THE SW 1/4 WAS COMPUTED AS SHOWN. MONUMENTS WERE THEN SET ACCORDING TO SAID DEED AND THE FOUND R/W MONUMENTS.

