

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: GEORGE BOURNE
3825 Calhoun Road
Medford, Oregon

PURPOSE: To monument and describe in two parcels the Bourne ownership in the North-half of the Southeast Quarter of the Northwest Quarter of Section 16, T38SR1W.

PROCEDURE: Found previous controls established on Recorded Survey No. 1541. Calculated the theoretical position of the West boundary of said Quarter-Quarter Section with respect to the centerline of Calhoun Road as shown.

In that the Bourne ownership and the adjacent ownership to the South indicate Government record distances, the South boundary of the Bourne ownership was monumented on the South boundary of the North-half of said Quarter-Quarter Section to eliminate mutual overlaps.

Monumented the parcels with 5/8" iron pins as shown, using for bearing control the Solar Meridian previously used on Recorded Survey No. 1541.

March 61

