



LEGEND

- = FOUND 5/8 x 30" IRON PIN WITH YELLOW PLASTIC CAP MARKED "FARBER FARBER PLS 2189" PER CITY OF MEDFORD ENGINEERING DRAWING 99-53 REFERENCES ON FILE WITH THE CITY SURVEYOR
- = SET 5/8 x 24" IRON PIN WITH YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
- = FOUND 5/8" x 30" IRON PIN WITH YELLOW PLASTIC CAP MARKED "FARBER PLS 2189" PER S/N 16288
- = FOUND 5/8" x 24" IRON PIN WITH YELLOW PLASTIC CAP MARKED "FARBER PLS 2189" PER S/N 16288 EXCEPT WHERE NOTED
- S/N = JACKSON COUNTY SURVEYOR'S OFFICE FILE NUMBER

* * RECEIVED * *

DATE MAR 14 2000 BY [Signature]

This survey consist of:
 L sheet(s) Map
 2 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]

OREGON
JULY 26, 1985
HERBERT A. FARBER
2189

RENEWAL DATE 12-31-01

ASSESSORS MAP FILE NO. 37 2W 35AD TL 801 & 37 2W 36BC TL 5101

**MAP OF SURVEY
PROPERTY LINE ADJUSTMENT**
in
Shelterfield Subdivision
LOCATED IN
NORTHEAST ONE QUARTER OF SECTION 35
and
NORTHWEST ONE QUARTER OF SECTION 36
TOWNSHIP 37 SOUTH, RANGE 2 WEST
WILLAMETTE MERIDIAN, CITY OF MEDFORD
JACKSON COUNTY, OREGON
for
SHELTER REEF PROPERTIES
3784 COLEMAN CREEK ROAD
MEDFORD, OREGON 97501

TABLE OF CURVES					
Curve	Δ = Delta	Radius	Length	Tangent	Chord Bearing & Distance
C1	90°11'10"	20.00'	31.48'	20.07'	S45°03'55"E - 28.33'
C2	64°15'09"	100.00'	112.14'	62.79'	N57°42'55"E - 106.36'
C3	64°24'39"	100.00'	112.42'	62.99'	N57°47'40"E - 106.59'
C4	125°17'42"	20.00'	43.74'	38.66'	N62°34'00"W - 35.53'
C5	29°11'48"	72.50'	36.94'	18.88'	S40°11'15"W - 36.55'
C6	34°52'46"	127.50'	77.62'	40.05'	S43°01'44"W - 76.42'
C7	29°22'23"	127.50'	65.36'	33.42'	S75°09'18"W - 64.65'
C8	89°56'18"	20.00'	31.39'	19.98'	S44°52'21"W - 28.27'
C9	64°15'09"	72.50'	81.30'	45.53'	N57°42'55"E - 77.11'
C10	15°02'34"	127.50'	33.47'	16.83'	N33°06'38"E - 33.38'
C11	37°34'32"	127.50'	83.63'	43.38'	N59°25'21"E - 82.14'
C12	78°07'56"	20.00'	27.27'	16.23'	N39°08'50"E - 25.21'

**SURVEY NARRATIVE
TO COMPLY WITH O.R.S. 209.250**

Purpose:
To survey and monument the property line adjustments as shown hereon.

Procedure:
Utilizing control established during the performance of Filed Survey No. 16144 and 16288 the adjusted lines were established as shown hereon.

- BASIS OF BEARING IS TRUE NORTH, NAD 83/91 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.
 - INST. NO. = INSTRUMENT NUMBER AS RECORDED IN THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.

Surveyed by:
FARBER & SONS, INC.
dba FARBER SURVEYING
(541) 776-0846

OFFICE LOCATION: 120 MISTLETOE MEDFORD, OREGON 97501
 MAILING ADDRESS: P.O. BOX 5286 CENTRAL POINT, OREGON 97502

SCALE: 1" = 50'
 DATE: MARCH 14, 2000
 JOB NO. 0472-98C
 DRAWING FILE: JOBS\SHELTERREEF\MOSPLA.FLX