



## Survey narrative to comply with ORS 209.250, Oregon State Law of 1947

For: Edward Gyger, 5310, Highway 66, Ashland, Oregon

Purpose: To establish the boundaries of tracts shown on this map.

Procedure: Began survey at the southeast corner of D. L. C. # 42 and surveyed the tracts according to the bearings and distances shown on the accompanying map.

## Detail of Claim corners from 1946 survey.

Sly. NE corner of Claim No. 42. Found the stone which I verified the position from one remaining original bearing tree in the southwest quadrant.

SE corner of D.L.C. # 42. Found the 1½" axle in place at the distance shown on the map from the southerly northeast corner and perpetuated this as follows:

A 10" white oak scribed L.S. B.T. bears N. 26° E. 77.8 feet.  
 A 16" " " " " " " " N. 0° 12' W. 199.6 feet.  
 No original bearing trees found.

SW corner of Claim No. 42. Found original B.T. (17" W. O. dead standing, bearing N. 40° W. 58 links, found stump of 12" W.O. N. 13° E. 126 links, no scribe visible, this stump checked for position of one original bearing trees. From these I set a 1" by 30" iron pipe according to the original field notes and perpetuated this corner as follows:

Scribed an 8" W. O., L.S. B.T. which bears N. 3° E. 31.95 feet.  
 " a 10" W. O., " " " " " S. 42° 15' W. 13.70 feet.  
 " an 11" W. O. " " " " " N. 70° 30' E. 41.47 feet.

NW corner D. L. C. 42. Found sandstone with X and 2 original B.Ts.

Along the north line of Claim No. 42 I found marble monuments with X on top which were witnessed by oak trees, the bearings and distances shown in Deed dated 1868 which gave the distances of the marble monuments from the northwest corner and the most northerly northeast corner of the Claim. From the most easterly marble monument I set a 1½ inch iron pipe for the northeast corner on the line between the monuments and the northwest corner of the Claim according to the distance set forth in the Deed description and perpetuated this as follows:

A 24" Black Oak scribed L.S. B. T. bears West 2.85 feet.  
 A 10" " " " " " " " S. 55° W. 64.50 feet.  
 The above corner also being the SE cor. of Claim # 41

Inside Ell corner ~~XXXXXX~~ of Claim No. 42 ( also SW cor. Claim # 43)

I set a 1½ inch iron pipe by original field note distances from the North northeast corner and the south northeast corner of the Claim and perpetuated this as follows.

Chiseled an X on top of a 4' x 4' x 4' boulder which bears S. 41° 50' E. 32.3 feet. Chiseled an X on the southeast bridge abutment which spans Neil Creek, which bears N. 50° E. 117.2 feet.  
 The above corner at highway R.W. northerly side.

