

16690

SURVEY FOR:

Larry Mulholland
P.O. Box 72
Shady Cove, OR. 97539

LOCATION:

N.W. 1/4 of Section 16,
T.34S., R.1W., W.M.,
Jackson County, Oregon

SURVEY BY:

Kaiser Surveying
19440 Highway 62
Eagle Point, OR. 97524

DATE:

October 17, 2000

** RECEIVED **

Date 10-18-00 By GJK

This survey consists of:

- 1 sheet(s) Map
- 0 page(s) Narrative

JACKSON COUNTY
SURVEYOR

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J.D.K.

OREGON
JULY 16, 1967
GARY D. KAISER
No. 803
EXP. 6-30-01

LEGEND

□ = Found 3/4" I. PIN
S.N. 3495

△ = Found 5/8" Rebar
S.N. 3495

○ = Found 5/8" Rebar
with Plastic Cap
S.N. 13047

⊘ = Found 5/8" Rebar
with Plastic Cap
S.N. 13736

● = Set 5/8" x 24" Rebar
with Plastic Cap marked
"KAISER RLS 803"

S.N. = Filed Survey Number
County Surveyors Office

() = Record/S.N. 3495

(()) = Record/S.N. 13047

((()) = Record/Inst. No. 95-24142 O.R.

(((()) = Record/Inst. No. 96-22324 O.R.

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: Boundary Survey of Tract described in Inst. No. 95-24142 O.R..
Also set lath on approximate 100' intervals on boundaries of the property.

PROCEDURE: The desired Boundaries were located using monuments set on Filed Survey Nos. 3495, 13047 & 13736 for control. The Southerly boundary was located deed record distance, 771.04', North from the C.W. 1/16 corner and ran East parallel with the North Boundary of Filed Survey No. 13736. The Northerly boundary was located deed record distance South, 275.00' from the N.W. 1/16 corner and ran to the existing monument at the N.E. corner of the Subject Property.

