

CORNER "B"

At the corner location I set a 5/8" by 30" iron pin with a 2" diameter Alum. Cap marked PLS 1086.

FROM WHICH:

A 7.5 inch diameter Douglas Fir bears S88°50'07"E 18.1 feet marked BT in one face.  
A 7.5 inch diameter Douglas Fir bears N57°19'21"W 22.8 feet marked BT in one face.

CORNER "C"

At the corner location I set a 5/8" by 30" iron pin with a 2" diameter Alum. Cap marked PLS 1086.

FROM WHICH:

A 6.5 inch diameter Douglas Fir bears N68°07'34"E 64.6 feet marked BT in one face.  
A 9 inch diameter Douglas Fir bears S60°10'19"W 40.6 feet marked BT in one face.

CORNER "D"

At the corner location I set a 5/8" by 30" iron pin with a 2" diameter Alum. Cap marked PLS 1086.

FROM WHICH:


A 13 inch diameter Black Oak bears N22°09'22"E 52.1 feet marked BT in one face.  
An 8 inch diameter Douglas Fir bears N37°52'20"W 91.2 feet marked BT in one face.

CORNER "E"


At the corner location I set a 5/8" by 30" iron pin with a 2" diameter Alum. Cap marked PLS 1086.

FROM WHICH:

A 4.5 inch diameter Steel Fence Post bears S89°30'45"E 53.4 feet marked with a 1" diameter Brass Washer stamped PLS 1086.  
A 4.5 inch diameter Steel Fence Post bears N73°52'59"E 52.6 feet marked with a 1" diameter Brass Washer stamped PLS 1086.



LICENSE RENEWAL DATE:  
DECEMBER 31,2002



## SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

LOCATION: Government Lots 1,2,3, and 4, and the Southeast Quarter of the Northeast Quarter of Section 1, Township 33 South, Range 2 East, Willamette Meridian, Jackson County, Oregon.

SURVEY FOR: Boise Cascade Corporation      David & Robyn Stearns  
Post Office Box 100      Post Office Box 225  
Medford, Oregon 97501      Prospect, Oregon 97536

SURVEY BY: Rambo Surveying  
Arthur Rambo      PLS 1086  
735 Vista Park Drive  
Eagle Point, Oregon 97524

DATE: December 15, 2000

BASIS OF BEARING: Jackson County Filed Survey Numbers 6960 and 7914

PURPOSE: Boundary Line Adjustment: Planning department file Number-2000-11-PLA, To adjust lot line between tax lots 102 and 200, 33-2E. To monument and mark new lot line between said tax lots 102 and 200 as shown on the plat to accompany this narrative.

PROCEDURE: A search of records revealed that there had been previous surveys along portions of said tax lots 102 and 200. Also, that there were 1" diameter iron pipes at the corners of that property described in Jackson County Deed Records, Volume 373 Page 177.  
A survey was run tying to corners needed for control of this survey. The new lot line was run, monumented, and marked as shown on the plat to accompany this narrative. Bearing trees and bearing objects were taken at the corners of the new lot line and referenced as corners A through E on the plat to accompany this narrative. This survey was completed only to mark the new lot line for "File No. 2000-11-PLA".

CORNERS SET THIS SURVEY: All measurements to bearing trees are to the center of tree at the base unless otherwise stated. All trees have a brass washer marked PLS 1086 nailed to the face of tree.

CORNER "A" At the corner location I set a 5/8" by 30" iron pin with a 2" diameter Alum. Cap marked PLS 1086.

FROM WHICH: A 4.5 inch diameter Madrona bears S82°26'45"W 25.9 feet marked BT in one face.  
A 7.5 inch diameter Madrona bears N12°00'45"W 28.7 feet marked BT in one face.