

T38S, R2 W, W.M.

Retracement of a Portion of the Section Line between Sections 30 and 31, According to Official Transcript of Original U.S. Field Notes, Furnished by Mr. Claude Williams of Jacksonville, Oregon

FEET

0.0 Corner of Sections 30 and 31, 25 and 36, as pointed out by Mr. Williams, I find an 8"x10"x8" UNMARKED STONE from which an

8"live oak, bears N40°E, 2.6 ft.
scribed S36-T38S-R3W

This corner is approximately 40 feet south of a draw that old notes call as 77.10Ch. South on a line between 25 and 30, total distance of 80ch. to corner.

Thence East on a blank line between sections 30 and 31, magnetic variation 20°30'E.

860.0 Top of spur ridge, course N.E.

1194.0 Draw, course N. (U.S. Notes call 1056.0 ft.)

1760.0 Spur ridge, course N.W.

2400.0 Top of ridge, course N40°W (U.S. Notes call 2211.0 ft.)

2954.7 Fall 17.6 ft. south of $\frac{1}{4}$ cor. Between 30 and 31. (U.S. notes call 2801.0 ft.) I find new B.T., a 9" B. Oak S48°W, 32.0 ft. From point for cor., as established by measurement from original 24" yellow pine B.T., N22°W, 11.2 ft. (now down and rotted, with scab of face present and scribe visible).

I offset to $\frac{1}{4}$ corner and continue East between 30 and 31.

3494.0 Draw, course N.E. (U.S. Notes call 3333.0)

3926.9 Fall 15.0 ft. south of a rock mound that Mr. Claude Williams states is the corner for 29,30,31 and 32. I cannot find any evidence of bearing trees to support this claim.

Done for Mr. Claude Williams, Feb. 17, 1961

Witness: R. Gledhill
R. Hause

