



Survey For Mr. Ralph Pierce  
 2100 Woodlawn Drive.  
 Medford, Oregon.

Located in D.L.C. 51, T 37S.R. 1 W  
 Jackson County, Oregon.

Date June 17, 1961.

REGISTERED  
 OREGON  
 LAND SURVEYOR

*L. N. Dow*

MAY 6, 1949  
 L. N. DOW  
 251

RECEIVED  
 JACKSON  
 JUN 29 1961  
 COUNTY  
 SURVEYOR



Scale 1" = 100'

Con. Mon. E. S. E. Cor. D. L. C. No. 51

5/8" bar f.

D.L.C. ELL Cor.  
 Mon. f

979.43

Written narrative to accompany plat for Survey NO.

Survey for Mr. Ralph Pierce, 2100 Woodlawn Dr. Medford, Oregon.

Survey made June 17, 1961.

Purpose to stake out 9.0 Acres for school tract.

Procedure: From a previous boundary survey we had the location of the E.S.E. corner of D.L.C. NO. 51, the monument at the Ell corner on the south line of D.L.C. 51, a 5/8" pin N 89°58'30"W 359.67 feet from the Ell corner, and a 5/8" pin North 822.0 feet from the last mentioned pin.

From the last mentioned 5/8" bar we ran East 37.09 feet and set a 5/8" Bar, then ran on the chord of a 606.62 foot radius curve to the left a distance of 242.57 feet and set a 5/8" bar, then ran N 66°56'E 31.14 feet and set a 5/8" bar, then ran on the bearing of N 68°04'30"E 24.02 feet and set a 5/8" bar for the northeast corner of the tract being surveyed. We then occupied the monument at the Ell corner of said D.L.C. No 51, and ran S 89° 52' 40"E on the D.L.C. Line a distance of 226.60 feet and set a 5/8" bar for the southeast corner of the tract as shown on the accompanying plat.

