

Survey For
DWIGHT H. FINDLEY
Located in Sec. 21, T. 37 S., R. 2 W. W.M.
By: Mark E. Boyden
June, 1961

17 16
20 21
Sec. cor.
Stone with 'X'
South 42.85'

Fd. 1" iron pipe - Westerly end
of monumented E. Ross
Lane.
14.91'
2.74'

Fd. 3/4" iron bolt - E. Ross Lane &
E. Old Stage Road by 1910
County Road Survey.

Rd. 1" iron pipe - E. Ross Lane &
E. Niedermyer Drive

East 887.65' S 89° 55' W 182.78'

30' 30'

ROAD

323.73'

SCALE: 1" = 50'

• Set 5/8" iron pin

1.66 ACRES

N 2° 43' 50" E 328.34'

NOVEMBER 9 1961

MARK E. BOYDEN

281

REGISTERED
OREGON
LAND SURVEYOR
Mark E. Boyden

S 18° 34' 50" W

S 85° 35' 30" E

271.09'

227.77'

30' 30'

S 75° 43' 50" E

365.37'

RECEIVED
JACKSON
JUL 15 1961
COUNTY &
SURVEYOR

Survey No. _____

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Dwight H. Findley
Old Stage Road
Medford, Oregon

PURPOSE: (1) To monument and describe a parcel in the Northwest corner of the Findley ownership.
(2) To monument and prepare a new description for the North boundary of the Fish Tract, to be finalized by a correction description from Findley to Fish, all being located in Lot No. 10 of L AND N SUB-DIVISION, NO. 1, Section 21, T37SR2W.

PROCEDURE:

Control for the 1910 road survey centerline of the Old Stage Road was derived from a Southerly projection of monuments found as set on Recorded Survey No. 871, after a search revealed the original pipe P.I. to the Southwest has been destroyed.

Other controls are shown on the attached map, setting 5/8" iron pins for property corners and using the Solar Meridian established previously on Recorded Survey No. 871.

June 1961

