

By finding the blazed pine tree with 21 growth rings over the blaze for the Northwest corner of that tract described in Volume 230, Page 527 of said Deed Records and the general alignment of the Fielder Creek Road, eliminated the possibility of said tract overlapping the subject surveyed parcel. However, it appears that the two adjoining tracts to the West (See Volume 230, Pages 296 and 295) could overlap this boundary of the subject surveyed parcel (which is located on the existing fence line).

No definite location of the Fielder Creek or West Evans Creek County Roads has been established at this time. Therefore, this survey was established to points in the existing roads, and witness corners set to establish side line control only, and the description prepared to except "all of that portion of the above-described property lying within the right-of-way of said county roads."



On a proportionate measurement and on line between the Northwest corner and the West Quarter corner of said Section 4, set a 3/4" x 36" galvanized iron pipe, 33" in the ground for the North one-sixteenth corner common to Sections 4 and 5, from which:

A 6" W. oak, scribed "RS 281-BT" bears South $89\frac{1}{4}^{\circ}$ East, 4.8 feet;

A 9" W. oak, scribed "RS 281-BT" bears South $6\frac{1}{2}^{\circ}$ West, 12.2 feet;

Found a 1" iron pipe, said to have been set by Surveyor Cap White, which bears North $28^{\circ} 25'$ East, 4.96 feet.

From the closed-loop random traverse, set 5/8" pin monuments as shown, basing the bearings on a solar observation taken on the West Evans Creek Road.



Survey Narrative to Comply with O.R.S. 209.250

FOR: R. C. Keusler and E. O. Leubcke
5533 E. Washington Blvd. c/o John R. Leubcke
Los Angeles 22, Calif. Rt. 1, Box 275, Rogue River, Ore.

PURPOSE: To monument and re-describe that property described in Volume 287, Page 444 of the Deed Records of Jackson County, Oregon, being located in Section 4, T36SR4W.

PROCEDURE:

Began at the 3/4" iron bolt set on the North boundary of Section 4 on Recorded Survey No. 1041, and traversed around the property, closing on the officially re-established Northwest corner of Section 4 and the random hubs set on said Recorded Survey No. 1041. Also traversed Southerly to the 1/4 corner common to Sections 4 and 5, where original evidence was found (see official re-establishment).

An effort was made to contact the present owners of those tracts of land lying Northerly from the Fielder Creek Road and immediately West of the West Evans Creek Road, so that their ambiguous descriptions (See Volume 230, Pages 295, 296, and 527 of the Deed Records of Jackson County, Oregon) could be re-described by this survey, but no cooperation could be obtained. However, the other adjoining owner along the Southerly boundary of this surveyed parcel, (See Volume 491, Page 332 of said Deed Records), who acquired all of the remaining property not previously segregated from the NW 1/4 of the NW 1/4 and the West 1/2 of the NE 1/4 of the NW 1/4 of said Section 4 lying Westerly from the West Evans Creek Road, agreed to Quit-Claim any of his interest within the boundaries established on this survey.