

MAP OF SURVEY

located in the  
SOUTHWEST ONE-QUARTER OF SECTION 4,  
TOWNSHIP 41 SOUTH, RANGE 2 EAST,  
WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON

for  
**KRIS AND ELIZABETH PRUSKO**

1009 KEVIN COURT #4  
PALATINE, ILLINOIS 60074

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Herbert A. Farber*  
OREGON  
JULY 26, 1985  
HERBERT A. FARBER  
2189

RENEWAL DATE 12-31-03

\*\*\* RECEIVED \*\*\*  
DATE 7-18-02 BY *BB*  
This survey consist of:  
1 sheet(s) Map  
2 page(s) Narrative  
JACKSON COUNTY  
SURVEYOR

LEGEND

- ✱ = FOUND STANDARD BLM PIPE AND BRASS CAP - PER RECORD 3" BRASS CAP ON 2 1/2" GALVANIZED IRON PIPE
- ⊗ = FOUND 2 1/2" BRASS CAP ON 1" GALVANIZED IRON PIPE PER JACKSON COUNTY SURVEYOR'S RECORDS
- = SET 5/8" x 30" IRON PIN w/ YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
- = APPROXIMATE HOMESITE LOCATION PER JACKSON COUNTY PLANNING DEPARTMENT FILE No. 89-50-SPR(OSR).
- S/N = RECORD FILED SURVEY NUMBER
- W.C. = WITNESS CORNER TO EAST RIGHT-OF-WAY OF PACIFIC HIGHWAY.
- BLM = BUREAU OF LAND MANAGEMENT

- BASIS OF BEARING IS TRUE NORTH, NAD 83/91 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.  
- RECORD SURVEY DATA IS SHOWN IN PARENTHESIS ADJACENT TO MEASURED SURVEY DATA WHERE APPLICABLE.  
- INST. No. = INSTRUMENT NUMBER AS RECORDED IN THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.

SURVEY NARRATIVE  
TO COMPLY WITH O.R.S. 209.250

PURPOSE: TO SURVEY AND MONUMENT THE PARCEL OF LAND DESCRIBED IN INSTRUMENT No. 01-31424 OF THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON, AS DIRECTED BY THE CLIENT.

PROCEDURE: I TIED THE SECTION CORNERS AND THE NORTH 1/4 CORNER TO SECTION 4 WITH GPS OBSERVATIONS. I THEN COMPUTED THE REMAINING 1/4 CORNERS, PER THE G.L.O. NOTES, AND MONUMENTED THE PARCEL AS SHOWN HEREON. OREGON STATE HIGHWAY DEPARTMENT DRAWING No. 5B-30-8, DATED DECEMBER, 1940, DOES NOT DEFINE THE EAST RIGHT-OF-WAY OF PACIFIC HIGHWAY ADJACENT TO MY CLIENT'S PROPERTY, THEREFORE, NO EFFORT WAS MADE TO LOCATE PACIFIC HIGHWAY ON THIS SURVEY. A DILIGENT SEARCH WAS MADE BY THIS OFFICE, AND THE STAFF OF THE COUNTY SURVEYOR'S OFFICE, PRIOR TO SETTING THE PROPORTION CORNERS AS SHOWN HEREON.

Surveyed by:  
**FARBER & SONS, INC.**  
dba FARBER SURVEYING  
(541) 776-0846

OFFICE LOCATION: 120 MISTLETOE MEDFORD, OREGON 97501  
MAILING ADDRESS: P.O. BOX 5286 CENTRAL POINT, OREGON 97502

SCALE: 1" = 500'  
DATE: AUGUST 5, 2002  
JOB NO.: 1028-01  
DRAWING FILE: JOBS\SISKIYOU\PRUSKO\_MOS.FLX

