



Survey No. 1750

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR: Mark A. Goldy  
18 North Front St.  
Medford, Oregon —

PURPOSE: To monument the outside boundaries of Lots 12-16  
inc. of Block 21 of the Original Town (now City)  
of Medford, Oregon.

PROCEDURE:

On a previous survey in this Block by Mr. C. Z.  
Boyden, controlling street centers were established from  
adjoining street monument controls and referenced.

The street centers on Front Street were then established  
from said references at the centerline intersections of  
East Main and East Sixth Streets.

The distance was then carefully measured, as was the  
angle in the Northeast quadrant of the centerline inter-  
section of Main and Front Streets, both of which agreed  
favorably with said previous survey.

Using the information of the previous Block survey for  
control of the remaining street centerlines, the property  
corners were then established by proportionate measurement.

Set property corner and witness corners as shown.

August 1961

