

PLAT

SHOWING A SURVEY SITUATED THE W1/2 OF SECTION 34, T.37S., R.4W., W.M., JACKSON COUNTY, OREGON.

LEGEND

- SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP MARKED "NYGREN LS1035".
 - FOUND MONUMENT AS NOTED.
 - () RECORD PER PENDING 1999 B.L.M. SURVEY.
 - MARKED LINE WITH BLAZES PAINTED FLO-RED AND FLO-RED RIBBON. (S'LY 10 ACRES LIES IN OPEN MEADOW, LINES NOT MARKED)
- BEARINGS BASED ON PENDING 1999 B.L.M. SURVEY FROM THE CENTER 1/4 COR. TO THE NORTH 1/4 COR.

NARRATIVE

THE PURPOSE IS TO SURVEY PARCEL 1 AND PARCEL 3 AS DESCRIBED IN DOCUMENT NO. 86-00567, JACKSON COUNTY RECORDS, AND MARK BOUNDARIES FOR LOGGING.

I RECOVERED AND HELD TO MONUMENTS SET BY B.L.M. WHICH WERE FOUND AS SHOWN ON ANNEXED PLAT.

SECTION 34 WAS SUBDIVIDED BY B.L.M. IN 1999. I CONTACTED RANDY ZANON, CADASTRAL SURVEYOR FOR B.L.M., AND HE EXPLAINED TO ME THAT THE 1999 SURVEY WAS PENDING AND BEING REVIEWED FOR APPROVAL BY THE CHIEF CADASTRAL SURVEYOR OF OREGON. RANDY ZANON FURNISHED ME WITH A MAP, LINE NOTES AND CORNER INFORMATION FOR THE PENDING 1999 B.L.M. SURVEY.

A NIKON DTM-A20LG TOTAL STATION WAS USED TO EXECUTE THIS SURVEY.

**** RECEIVED ****
 Date 11-22-02 By *BB*
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
 JACKSON COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR
Gerald V. Nygren
 OREGON
 GERALD V. NYGREN
 AUGUST 22, 1975
 1035
 RENEW: 12-31-02

SURVEYED FOR:
 ROUGH & READY LBR. CO.
 30365 REDWOOD HWY.
 CAVE JUNCTION, OR 97523

SURVEYED FOR:
 SISKIYOU ENTERPRISE, LLC
 P.O. BOX 324
 GLENDALE, OR 97442

GERALD V. NYGREN
 522 BARKER DRIVE
 MERLIN, OREGON 97532

DATE: OCT. 22, 2002
 SCALE: 1" = 200'
 JOB NO. 02-41

