

MAP OF SURVEY

LOCATED IN:
 THE N.W. 1/4 OF SECTION 3, T.35S., R.1W., W.M.,
 JACKSON COUNTY, OREGON
 FOR:
 HUYCKE, MAULDING, O'CONNOR & JARVIS, LLP
 502 WEST MAIN STREET, SUITE 102
 MEDFORD, OREGON 97501

**SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
 OREGON REVISED STATUTES**

PURPOSE: TO SURVEY, MONUMENT AND PREPARE MAP OF SURVEY OF SUBJECT PROPERTY.

PROCEDURE: UTILIZING FOUND MONUMENTATION AND INFORMATION PER FILED SURVEYS NO. 9459, 11707, 13743, 15146, AND 15309 FOR CONTROL, I ESTABLISH PROPER MONUMENTS AS SHOWN HEREON. I RAN A TRAVERSE FROM THE NORTHWEST CORNER OF SECTION 3, TO THE NORTH 1/4 CORNER OF SECTION 3 TO THE SOUTH 1/4 CORNER OF SECTION 3. MY MEASUREMENTS WERE VERY CLOSE TO THE INFORMATION PER FILED SURVEY NO. 9459. THEREFORE, I USED FILED SURVEY NO. 9459 FOR THE BASIS OF BEARING AND TO DETERMINE THE PROPORTIONATE COMPUTATIONS OF THE NORTH-WEST 1/4 OF SECTION 3. AN ELECTRONIC TOTAL STATION WAS USED TO MAKE ALL MEASUREMENTS.

INSTRUMENT NO. 97-33552 OF
 THE DEED RECORDS OF JACKSON
 COUNTY, OREGON

Douglas C. McMah
 RENEWS 12/31/04

HOFFBUHR & ASSOCIATES, INC.
 3155 ALAMEDA STREET, SUITE 201
 MEDFORD, OREGON 97504
 (541) 779-4641

BY: DOUGLAS C. McMAHAN PLS No. 1913
 SCALE: 1" = 200' April 29, 2003
 BASIS OF BEARING: S/N 9459 (North-South
 Centerline of Section 3)

- = Set 5/8"x24" rebar with plastic cap stamped "D.McMAHAN LS 1913"
- ⊙ = Found brass disc monument as shown
- = Found 5/8" iron pin as shown
- = Found 5/8" iron pin with metal cap per S/N 13743
- S/N = Filed Survey Number
- x- = Fenceline
- N.T.S. = Not To Scale

**** RECEIVED ****
 Date 5-2-03 By DB
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
 JACKSON COUNTY
 SURVEYOR

