



SURVEY
LOTS 1,2,3,4,5,6
BLOCK I
LEWIS SUBDIVISION
JACKSONVILLE, OREGON
SCALE: 1"=100' HUGH C. INGLE
SEPT. 1961 CIVIL ENGINEER

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250
OREGON REVISED STATUTES

FOR: Mrs. Céora Cooney.

PURPOSE: To establish corners on lots in Block 1 Lewis Subdivision in the Town of Jacksonville.

PROCEEDURE: Center line of Fifth Street was projected south from the monument in the center of California Street and Fifth Street, backsighting North to 30 foot offset from west property line in Block 19 and monument near F Street. Set center line point on Fifth on south side of Oak Street. This checked for record distance from 3/4" pipe found at Southeast corner of 3 3rd. and Oak . Line produced south and found remains of old stake corresponding to Southwest corner of Block 4 Lewis Addition at corresponding distance. another stake was found on center line and corresponded with my line produced.

Measured record distance from south property line on California Street and established Lot corners in accordance with subdivision plat.

Hugh C. Ingle
Hugh C. Ingle.
Civil Engineer

