

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

FOR:

James C. Miller
P.O. Box 3512
Ashland, OR 97520

LOCATION:

The Southeast One Quarter of Section 25, Township 38 South, Range 2 East

PURPOSE:

To monument and describe the tract of land as shown on the accompanying map for Property Line Adjustment purposes.

PROCEDURE:

This tract is involved in a series of ongoing property line adjustments that were not required to be surveyed by Jackson County Planning, all being over ten acres. However, due to specific directions from the client as to the location of the boundaries, I was directed to monument and describe said tract so that it would be more certain than a paper description.

The South $\frac{1}{4}$ corner of Section 25 being the Southeast corner of one of the tracts involved in the property line adjustments was requested by the client to be monumented. Accordingly, a traverse was run between the Southwest and Southeast corners of Section 25, from which said $\frac{1}{4}$ corner was monumented on a proportional basis as shown on the accompanying map. No evidence of the original rock mound was found. Moreover, this corner falls in a very rocky meadow making it almost impossible to discern any remains that could have scattered. The location for all other monuments set by this survey was established according to the client's instructions. A 6-foot steel T-bar fence post was set alongside all of the monuments set by this survey.

BY:

George Burrell, PLS
2305-C Ashland Street #261
Ashland, Oregon 97520
Oct. 25, 2003

REGISTERED
PROFESSIONAL
LAND SURVEYOR

George Burrell

OREGON
JULY 10, 1964
GEORGE R. BURRELL
638

Exp. 12/31/03

**** RECEIVED ****
Date 11-7-03 By _____
This survey Consists of:
1 sheet(s) Map
1 page(s) Narrative
JACKSON COUNTY
SURVEYOR

