



MAP OF SURVEY
 located in the
 SOUTHWEST ONE QUARTER OF SECTION 16,
 TOWNSHIP 34 SOUTH, RANGE 1 EAST,
 WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON
 for
CLIFF BARROWS
 PO BOX 1164
 EAGLE POINT, OREGON 97524

LEGEND

- ⊠ = FOUND STANDARD BLM BRASS CAP PER - SECTION CORNER
- ⊞ = 1/4 SECTION CORNER
- = PREVIOUSLY TIED MONUMENT AS DESCRIBED
- = SET 5/8" x 24" IRON PIN w/ YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
- S/N = RECORD FILED SURVEY NUMBER

- BASIS OF BEARING IS TRUE NORTH, NAD 83/91 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.
 - RECORD SURVEY DATA IS SHOWN IN PARENTHESIS ADJACENT TO MEASURED SURVEY DATA WHERE APPLICABLE.

**SURVEY NARRATIVE
 TO COMPLY WITH O.R.S. 209.250**

PURPOSE: TO SURVEY AND MONUMENT THE SOUTH AND EAST LINE OF THE SOUTHWEST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 16 IN TOWNSHIP 34 SOUTH, RANGE 1 EAST, WILLAMETTE MERIDIAN.

PROCEDURE: USING CONTROL ESTABLISHED IN S/N 11657 AND THIS SURVEY I TIED THE SOUTHWEST CORNER AND THE SOUTHEAST CORNER OF SAID QUARTER SECTION. I THEN SET THE WEST 1/16 CORNER OF SAID QUARTER SECTION AT THE MIDPOINT BETWEEN THE TWO MONUMENTS. I THEN ESTABLISHED THE CENTER OF SAID QUARTER SECTION USING RECORD SURVEY DATA FROM S/N 11657 AND DATA FROM THIS SURVEY.
 SEE S/N 11283 FOR AND S/N 11657 FOR SECTION BREAKDOWN.

| | |
|---|---|
| REGISTERED PROFESSIONAL LAND SURVEYOR <i>Herbert A. Farber</i> | ** RECEIVED ** DATE 5-7-04 BY <i>BB</i> This survey consists of: 1 sheet(s) Map 2 page(s) Narrative JACKSON COUNTY SURVEYOR |
| OREGON JULY 26, 1985 HERBERT A. FARBER 2189 RENEWAL DATE 12-31-05 | |

Surveyed by:
FARBER & SONS, INC.
 dba FARBER SURVEYING
 (541) 664-5599
 PO BOX 5286
 431 OAK STREET
 CENTRAL POINT, OREGON 97502

SCALE: 1" = 200'
 DATE: FEBRUARY 16, 2004
 JOB NO.: 1197-03
 DRAWING FILE: JOBS\shady cove NE Co\crowfoot road\map of survey 011904.flx