

MARK E. BOYDEN  
R.P.L.S. ORE. 281  
108 MISTLETOE ST., MEDFORD, OREGON 97501  
PHONE (503) 773-6000

SURVEY NO. 18316<sub>h</sub>

**SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250**

**SURVEY FOR:** Ron Bray  
4756 Fern Valley Road  
Medford, OR 97504

**SURVEY BY:** Boyden Surveyors  
108 Mistletoe Street  
Medford, OR 97501

**LOCATION:** NE ¼, Section 11, T. 38 S., R. 1 W., W.M.  
Jackson County, Oregon

**BASIS OF BEARINGS:** East line of D.L.C. No. 81,  
Re: County Filed Survey No. 2375.


**DATE:** June 14, 2004

**PURPOSE:** To monument the South boundary of the Bray property  
as described as Parcel No. 1, Instrument No. 97-00531.

**PROCEDURE:** Utilizing a Nikon Top-Gun E.D.M., tied to monuments  
shown. The record angle at the Southeast property  
corner was considered better control than the witness  
corner pin found near the Southwest property corner,  
found alongside of a fence corner.


The U-Bar monument found near the most-Westerly-  
Northwest property corner may be the best evidence for  
identifying the creek meander line as described in Deed  
Volume 128, Page 370 in 1909.

From said data, set monuments to control said South  
property line as shown on the map to accompany this  
report.



*Mark E. Boyden*  
OREGON  
REGISTERED  
MARK E. BOYDEN  
281

Expires: 12/31/05



•• RECEIVED ••

Date 6-25-04 By MB

This survey Consists of:

1 sheet(s) Map

1 page(s) Narrative

JACKSON COUNTY  
SHERIFF

