



*** RECEIVED ***
 DATE 11-4-04 BY [Signature]
 This survey consists of:
 1 sheet(s) Map
 0 page(s) Narrative
 JACKSON COUNTY SURVEYOR

S.W. CORNER LOT 4
 5/8" PIN FOUND SEVERLY BENT TO NORTH EAST (SEE NARRATIVE)

MAP OF SURVEY
 located in the
 SOUTHEAST ONE QUARTER OF SECTION 36,
 TOWNSHIP 36 SOUTH, RANGE 2 WEST,
 WILLAMETTE MERIDIAN, JACKSON COUNTY, OREGON
 for
OLDLAND FAMILY TRUST
 F.O. BOX 3241
 CENTRAL POINT, OR 97502

LEGEND

- ⌘ = FOUND 2 1/2" BRASS CAP-1/4 SECTION CORNER
- = FOUND 5/8" IRON PIN, "FARBER P.L.S. 2189" OR AS DESCRIBED
- = SET 5/8" x 24" II" ON PIN w/ YELLOW PLASTIC CAP MARKED "FARBER PLS 2189"
- S/N = RECORD FILED SURVEY NUMBER
- () = RECORDED INFORMATION PER SURVEY NUMBER 15015
- [] = RECORDED INFORMATION PER SURVEY NUMBER 9673

- BASIS OF BEARING IS TRUE NORTH, NAD 83/91 DATUM, AS DERIVED BY GLOBAL POSITIONING SYSTEM OBSERVATIONS.
 - INST. No. = INSTRUMENT NUMBER AS RECORDED IN THE OFFICIAL RECORDS OF JACKSON COUNTY, OREGON.
 - PUE = PUBLIC UTILITY EASEMENT FOR WATER, SANITARY SEWER, STORM DRAIN, PHONE, GAS, AND CABLE TV.

SURVEY NARRATIVE TO COMPLY WITH O.R.S. 209.250

PURPOSE: TO SURVEY AND MONUMENT THE BOUNDARY LINES OF LOTS 9 AND 10 FROM RECORDED PLATS OF TABLE ROCK INDUSTRIAL PARK AND BIERSON INDUSTRIAL PARK, RECORDED SURVEY NUMBERS 9673 AND 15015.

PROCEDURE: USING CONTROL ESTABLISHED IN PREVIOUS SURVEYS I TIED THE FOUND MONUMENTS AS SHOWN HEREON. THE SOUTHWEST CORNER OF LOT 4 WAS SET NORTHEASTERLY. THIS PIN WAS TIED WHERE IT ENTERED THE GROUND STRAIGHT. ALL OTHER MONUMENTS WERE FOUND IN GOOD CONDITION. THE RIGHT-OF-WAY WAS HELD TO BE ALONG THE LINE BETWEEN THE SOUTHWEST CORNER OF LOT 4 AND THE SOUTHEAST CORNER OF LOT 10. THE EAST LINE OF LOT 10 WAS HELD TO BE THE LINE BETWEEN THE FOUND MONUMENTS AS SHOWN HEREON. I THEN RAN LINES PARALLEL TO SAID EAST LINE OF LOT 10 FROM THE MONUMENTS FOUND AT NORTHEAST AND NORTHWEST CORNER OF LOT 9. I INTERSECTED THESE LINES WITH THE NORTH RIGHT OF WAY LINE AND SET MONUMENTS AT THE RESPECTIVE INTERSECTIONS.

REGISTERED PROFESSIONAL LAND SURVEYOR
 [Signature]
 OREGON JULY 26, 1985
 HERBERT A. FARBER 2189
 RENEWAL DATE 12-31-05

Surveyed by:
FARBER & SONS, INC.
 dba FARBER SURVEYING
 (541) 664-5599
 170 BOX 5286
 431 OAK STREET
 CENTRAL POINT, OREGON 97502

SCALE: 1" = 50'
 DATE: NOVEMBER 2nd, 2004
 JOB NO.: 346-93
 DRAWING FILE: JOBS\Medford_NE\Willas-Road-West\Oldland\Micro\MapOfSurvey.FLX

